

UNITED STATES GOVERNMENT  
MEMORANDUM

October 3, 2019

To: Public Information (MS 5030)  
From: Plan Coordinator, FO, Plans Section (MS  
5231)

Subject: Public Information copy of plan

Control # - S-07967

Type - Supplemental Development Operations Coordinations Document

Lease(s) - OCS- 00375 Block - 42 Main Pass Area  
OCS-G01367 Block - 42 Main Pass Area  
OCS-G01372 Block - 55 Breton Sound Area  
OCS-G01452 Block - 43 Main Pass Area

Operator - Cantium, LLC

Description - Caissons FA, FAB, Wells FAB1, FAB2, FAB3, FA010, FA013

Rig Type - Not Found

Attached is a copy of the subject plan.

It has been deemed submitted as of this date and is under review for approval.

Robert Arpino  
Plan Coordinator

Site Type/Name	Botm Lse/Area/Blk	Surface Location	Surf Lse/Area/Blk
CAIS/FA		2302 FSL, 1875 FWL	G01372/BS/55
FIXED/FAB		2300 FSL, 1869 FWL	G01372/BS/55
WELL/FA010	G01372/BS/55	2302 FSL, 1874 FWL	G01372/BS/55
WELL/FA013	G01367/MP/42	2305 FSL, 1870 FWL	G01372/BS/55
WELL/FAB1	00375/MP/42	2332 FSL, 1889 FWL	G01372/BS/55
WELL/FAB2	G01452/MP/43	2326 FSL, 1877 FWL	G01372/BS/55
WELL/FAB3	G01452/MP/43	2322 FSL, 1883 FWL	G01372/BS/55
WELL/FAB4	G01372/BS/55	2318 FSL, 1890 FWL	G01372/BS/55

**PUBLIC COPY**  
July 8, 2019

## **SUPPLEMENTAL DEVELOPMENT OPERATIONS COORDINATION DOCUMENT**



Breton Sound Block 55  
OCS-G 01372  
Main Pass Block 40 Field Unit  
Agreement No. 891003847

**Estimated Startup Date: November 5, 2019**

**SUBMITTED BY:**

Cantium, LLC  
111 Park Place Drive, Suite 100  
Covington, LA 70433

Susan Alonso  
(832) 434-5031

[susan.alonso@cantium.us](mailto:susan.alonso@cantium.us)

**AUTHORIZED REPRESENTATIVE:**

Dena Rodriguez  
J. Connor Consulting, Inc.  
19219 Katy Freeway, Suite 200  
Houston, Texas 77094  
(281) 698-8512

[dena.rodriguez@jccteam.com](mailto:dena.rodriguez@jccteam.com)





## TABLE OF CONTENTS

<b>SECTION 1 PLAN CONTENTS .....</b>	<b>1</b>
1.1 PLAN INFORMATION.....	1
1.2 LOCATION.....	1
1.3 SAFETY AND POLLUTION PREVENTION FEATURES .....	1
1.4 STORAGE TANKS AND PRODUCTION VESSELS.....	2
1.5 POLLUTION PREVENTION MEASURES .....	2
1.6 ADDITIONAL MEASURES.....	2
1.7 COST RECOVERY FEE .....	2
<b>SECTION 2 GENERAL INFORMATION.....</b>	<b>3</b>
2.1 APPLICATIONS AND PERMITS.....	3
2.2 DRILLING FLUIDS .....	3
2.3 PRODUCTION .....	3
2.4 OIL CHARACTERISTICS.....	3
2.5 NEW OR UNUSUAL TECHNOLOGY .....	3
2.6 BONDING STATEMENT.....	3
2.7 OIL SPILL FINANCIAL RESPONSIBILITY (OSFR).....	4
2.8 DEEPWATER WELL CONTROL STATEMENT.....	4
2.9 SUSPENSION OF PRODUCTION.....	4
2.10 BLOWOUT SCENARIO AND WORST CASE DISCHARGE CALCULATIONS.....	4
<b>SECTION 3 GEOLOGICAL AND GEOPHYSICAL INFORMATION .....</b>	<b>8</b>
3.1 GEOLOGICAL DESCRIPTION .....	8
3.2 STRUCTURE CONTOUR MAPS.....	8
3.3 INTERPRETED SEISMIC LINES.....	8
3.4 GEOLOGICAL STRUCTURE CROSS-SECTIONS .....	8
3.5 SHALLOW HAZARDS REPORT.....	8
3.6 SHALLOW HAZARDS ASSESSMENT .....	8
3.7 HIGH-RESOLUTION SEISMIC LINES.....	8
3.8 STRATIGRAPHIC COLUMN.....	8
3.9 TIME VS DEPTH TABLES .....	8
<b>SECTION 4 HYDROGEN SULFIDE INFORMATION .....</b>	<b>9</b>

4.1 CONCENTRATION .....	9
4.2 CLASSIFICATION.....	9
4.3 H <sub>2</sub> S CONTINGENCY PLAN .....	9
4.4 MODELING REPORT .....	9
<b>SECTION 5 MINERAL RESOURCE CONSERVATION INFORMATION.....</b>	<b>10</b>
5.1 TECHNOLOGY & RESERVOIR ENGINEERING PRACTICES AND PROCEDURES .....	10
5.2 TECHNOLOGY AND RECOVERY PRACTICES AND PROCEDURES .....	10
5.3 RESERVOIR DEVELOPMENT .....	10
<b>SECTION 6 BIOLOGICAL, PHYSICAL AND SOCIOECONOMIC INFORMATION.....</b>	<b>11</b>
6.1 DEEPWATER BENTHIC COMMUNITIES .....	11
6.2 TOPOGRAPHIC FEATURES (BANKS) .....	11
6.3 TOPOGRAPHIC FEATURES STATEMENT (SHUNTING).....	11
6.4 LIVE-BOTTOMS (PINNACLE TREND FEATURES).....	11
6.5 LIVE BOTTOMS (LOW RELIEF).....	11
6.6 POTENTIALLY SENSITIVE BIOLOGICAL FEATURES .....	11
6.7 THREATENED AND ENDANGERED SPECIES, CRITICAL HABITAT AND MARINE MAMMAL INFORMATION.....	11
6.8 ARCHAEOLOGICAL REPORT .....	13
6.9 AIR AND WATER QUALITY INFORMATION .....	13
6.10 SOCIOECONOMIC INFORMATION .....	13
<b>SECTION 7 WASTES AND DISCHARGES INFORMATION .....</b>	<b>14</b>
7.1 PROJECTED GENERATED WASTES .....	14
7.2 MODELING REPORT .....	14
<b>SECTION 8 AIR EMISSIONS INFORMATION .....</b>	<b>15</b>
8.1 EMISSIONS WORKSHEETS AND SCREENING QUESTIONS.....	15
8.2 SUMMARY INFORMATION .....	15
<b>SECTION 9 OIL SPILL INFORMATION .....</b>	<b>16</b>
9.1 OIL SPILL RESPONSE PLANNING .....	16
9.2 SPILL RESPONSE SITES .....	16
9.3 OSRO INFORMATION.....	16
9.4 WORST-CASE DISCHARGE SCENARIO DETERMINATION .....	16
9.5 OIL SPILL RESPONSE DISCUSSION .....	17
9.6 MODELING REPORT .....	17

<b>SECTION 10 ENVIRONMENTAL MONITORING INFORMATION</b> .....	<b>18</b>
10.1 MONITORING SYSTEMS .....	18
10.2 INCIDENTAL TAKES .....	18
10.3 FLOWER GARDEN BANKS NATIONAL MARINE SANCTUARY .....	18
<b>SECTION 11 LEASE STIPULATIONS INFORMATION</b> .....	<b>19</b>
11.1 MARINE PROTECTED SPECIES.....	19
<b>SECTION 12 ENVIRONMENTAL MITIGATION MEASURES INFORMATION</b> .....	<b>21</b>
12.1 MEASURES TAKEN TO AVOID, MINIMIZE, AND MITIGATE IMPACTS .....	21
12.2 INCIDENTAL TAKES .....	21
<b>SECTION 13 RELATED FACILITIES AND OPERATIONS INFORMATION</b> .....	<b>22</b>
13.1 RELATED OCS FACILITIES AND OPERATIONS.....	22
13.2 TRANSPORTATION SYSTEM .....	22
13.3 PRODUCED LIQUID HYDROCARBONS TRANSPORTATION VESSELS.....	22
<b>SECTION 14 SUPPORT VESSELS AND AIRCRAFT INFORMATION</b> .....	<b>23</b>
14.1 GENERAL .....	23
14.2 DIESEL OIL SUPPLY VESSELS .....	23
14.3 DRILLING FLUID TRANSPORTATION .....	23
14.4 SOLID AND LIQUID WASTE TRANSPORTATION.....	23
14.5 VICINITY MAP .....	23
<b>SECTION 15 ONSHORE SUPPORT FACILITIES INFORMATION</b> .....	<b>24</b>
15.1 GENERAL .....	24
15.2 SUPPORT BASE CONSTRUCTION OR EXPANSION.....	24
15.3 SUPPORT BASE CONSTRUCTION OR EXPANSION TIMETABLE .....	24
15.4 WASTE DISPOSAL.....	24
<b>SECTION 16 COASTAL ZONE MANAGEMENT (CZM) INFORMATION</b> .....	<b>25</b>
<b>SECTION 17 ENVIRONMENTAL IMPACT ANALYSIS (EIA)</b> .....	<b>27</b>
<b>SECTION 18 ADMINISTRATIVE INFORMATION</b> .....	<b>28</b>
18.1 EXEMPTED INFORMATION DESCRIPTION.....	28

## SECTION ATTACHMENTS

<b>Section 1</b>	<b>Plan Contents</b>
1-A	OCS Plan Information Form
1-B	Well Location Plat
1-C	Pay.gov Receipt
<b>Section 2</b>	<b>General Information</b>
2-A	SDS
<b>Section 7</b>	<b>Wastes and Discharges Information</b>
7-A	Waste You Will Generate, Treat and Downhole Dispose or Discharge to the GOM
<b>Section 8</b>	<b>Air Emissions Information</b>
8-A	Emissions Worksheets
<b>Section 9</b>	<b>Oil Spill Information</b>
9-A	Oil Spill Response Discussion
<b>Section 14</b>	<b>Support Vessels and Aircraft Information</b>
14-A	Waste You Will Transport and/or Dispose Onshore Table
14-B	Vicinity Map
<b>Section 16</b>	<b>Coastal Zone Management (CZM) Information</b>
16-A	Coastal Zone Consistency Certifications
<b>Section 17</b>	<b>Environmental Impact Analysis (EIA)</b>
17-A	Environmental Impact Analysis (EIA)

## SECTION 1 PLAN CONTENTS

### 1.1 PLAN INFORMATION

Lease OCS-G 01372, Breton Sound Block 55 was issued May 1, 1964. Lease OCS 00375, Main Pass Block 42 was issued August 5, 1947. Lease OCS-G 01452, Main Pass Block 43 was issued May 1, 1966. Lease OCS-G 01367, Main Pass Block 42 was issued May 1, 1964. The leases are held by unit production. Caisson FA was installed on January 1, 1966. Cantium, LLC (Cantium) was designated operator of Leases OCS-G 01372, 01452 and 01367 effective July 24, 2017 and Lease OCS 00375 effective July 20, 2017. These leases are in the Main Pass Block 40 Field Unit, Contract No. 891003847, which was approved effective September 9, 2002.

Under this Supplemental Development Operations Coordination Document (DOCD), Cantium proposes to drill, complete, test and place three wells on production, and drill and complete one well as a dumpflood well. The proposed wells will be drilled and produced from the BS 55 FAB platform, which will be set adjacent to the existing BS 55 FA Caisson. The FAB structure will be a dual level well protector platform supported by a 48" caisson with a 20" internal well conductor and three 20" exterior well conductors. The FAB1 well path proceeds from the FAB Platform in BS 55, Lease OCS-G 01372, crosses MP 42, Lease OCS-G 01367, and bottom-holes in MP 42 Lease OCS 00375. The BS 55 FAB2 and BS 55 FAB3 well paths both proceed from the FAB Platform in BS 55, Lease OCS-G 01372, cross BS 54, Lease OCS-G 01452, and bottom-hole in MP 43 Lease OCS-G 01452. The FAB4 well path proceeds from the FAB Platform in BS 55, Lease OCS-G 01372 and bottom-holes within the same lease. A 6" x 6000' long bulk oil pipeline will be installed to BS 55 F to support the increased liquid production rate.

These development operations are in approximately 28-39 feet of water. The wells will be drilled with a jackup MODU.

The OCS Plan Information Form BOEM-137 is included as **Attachment 1-A**.

### 1.2 LOCATION

Well Location Plats depicting the proposed FAB structure, surface locations and bottomhole locations of the proposed wells, measured depths/true vertical depths and water depths is included as **Attachment 1-B**.

No anchors are associated with the activities proposed in this plan.

### 1.3 SAFETY AND POLLUTION PREVENTION FEATURES

A description of the drilling unit which complies with all relevant regulations is included on the OCS Plan Information Form. Rig specifications will be made part of each Application for Permit to Drill.



The rig will be equipped with safety and fire-fighting equipment required to comply with United States Coast Guard (USCG) regulations. Appropriate lifesaving equipment such as life rafts, life jackets, ring buoys, etc. as prescribed by the USCG, will be maintained on the rig at all times.

Safety features on the drilling unit will include well control, pollution prevention, and blowout prevention equipment as described in BSEE regulations 30 CFR 250 C, D, E, O, Q and S; and as further clarified by BSEE Notices to Lessees, and current policy making invoked by the BSEE, Environmental Protection Agency (EPA) and the USCG.

Pollution prevention measures include installation of curbs, gutters, drip pans, and drains on drilling deck areas to collect all contaminants and debris. Compliance will be maintained with the EPA NPDES Permit. The rig will be monitored daily and any waste or fuel resulting in pollution of the Gulf waters will be reported to the representative in charge for immediate isolation and correction of the problem. All spills will be reported to the appropriate governmental agencies.

#### 1.4 STORAGE TANKS AND PRODUCTION VESSELS

The table below provides storage tanks with capacity of 25 barrels or more that will store fuels, oil and lubricants.

Type of Storage Tank	Type of Facility	Tank Capacity (bbl)	Number of Tanks	Total Capacity (bbl)	Fluid Gravity (API)
Fuel oil (marine diesel)	MODU	1,741	2	3,482	32.4°
Production	MODU	25	2	50	26°

#### 1.5 POLLUTION PREVENTION MEASURES

These operations do not propose activities for which the State of Florida is an affected state.

#### 1.6 ADDITIONAL MEASURES

Cantium does not propose any additional safety, pollution prevention, or early spill detection measures beyond those required by 30 CFR Part 250.

#### 1.7 COST RECOVERY FEE

Documentation of the \$12,714 cost recovery fee payment is included as **Attachment 1-C**.

## ATTACHMENT 1-A

U.S. Department of the Interior  
Bureau of Ocean Energy Management

OMB Control Number: 1010-0151  
OMB Approval Expires: 6/30/2021

## OCS PLAN INFORMATION FORM

General Information												
Type of OCS Plan:		Exploration Plan (EP)	X	Development Operations Coordination Document (DOCD)								
Company Name: Cantium, LLC				BOEM Operator Number: 03481								
Address: 111 Park Place Drive, Suite 100				Contact Person: Dena Rodriguez								
Covington, LA 70433				Phone Number: 281-698-8512								
				E-Mail Address: <a href="mailto:dena.rodriguez@jccteam.com">dena.rodriguez@jccteam.com</a>								
If a service fee is required under 30 CFR 550.125(a), provide the				Amount paid	\$12,714	Receipt No.			26IHADTA			
Project and Worst Case Discharge (WCD) Information												
Lease: OCS-G 01372			Area: Breton Sound			Block: 55			Project Name: N/A			
Objectives:	X	Oil	X	Gas		Sulphur		Salt	Onshore Support Bases: Venice, LA; Golden Meadow, LA			
Platform / Well Name: FAB1				Total Volume of WCD: 21,802 bbls/day				API Gravity: 33°				
Distance to Closest Land (Miles): 8.7				Volume from uncontrolled blowout: 1,308,120 bbls								
Have you previously provided information to verify the calculations and assumptions for your WCD?								Yes	X	No		
If so, provide the Control Number of the EP or DOCD with which this information was provided												
Do you propose to use new or unusual technology to conduct your activities?								Yes	X	No		
Do you propose to use a vessel with anchors to install or modify a structure?								Yes	X	No		
Do you propose any facility that will serve as a host facility for deepwater subsea development?								Yes	X	No		
Description of Proposed Activities and Tentative Schedule (Mark all that apply)												
Proposed Activity				Start Date			End Date			No. of Days		
Installation of Structure				11/05/2019			11/17/2019			13		
Installation of Pipeline – Riser and Spools				11/15/2019			11/22/2019			8		
Drill, Complete – Well No. FAB4				12/01/2019			12/30/2019			30		
Complete Installation of Pipeline				02/10/2020			02/13/2020			4		
Start Injection – Well No. FAB4				02/14/2020			02/14/2025			5 year reserve life		
Drill, Complete, Test, Commence Production – Well No. FAB3				02/15/2020			03/16/2020			30		
Production – Well No. FAB3				03/17/2020			03/17/2025			5 year reserve life		
Drill, Complete, Test, Commence Production – Well No. FAB2				03/18/2020			04/16/2020			30		
Production – Well No. FAB2				04/17/2020			04/17/2025			5 year reserve life		
Drill, Complete, Test, Commence Production – Well No. FAB1				04/18/2020			08/20/2020			125		
Production – Well No. FAB1				08/21/2020			08/21/2025			5 year reserve life		
Future Well Intervention Activities – Wells on structures FA, FAB				01/01/2021			12/31/2030			150 days/year		
Description of Drilling Rig						Description of Structure						
X	Jackup			Drillship		X	Caisson			Tension leg platform		
	Gorilla Jackup			Platform rig			Fixed platform			Compliant tower		
	Semisubmersible			Submersible			Spar			Guyed tower		
	DP Semisubmersible			Other (Attach description)			Floating production system			Other (Attach description)		
Drilling Rig Name (If known): Enterprise 264 or equivalent jackup												
Description of Lease Term Pipelines												
From (Facility/Area/Block)			To (Facility/Area/Block)			Diameter (Inches)			Length (Feet)			
FAB / BS / 55			F / BS / 55			6			6,000'			

**OCS PLAN INFORMATION FORM (CONTINUED)**  
**Include one copy of this page for each proposed well/structure**

Proposed Well/Structure Location									
Well or Structure Name/Number (If renaming well or structure, reference previous name): FA				Previously reviewed under an approved EP or DOCD?		X	Yes		No
Is this an existing well or structure?		X	Yes	No	If this is an existing well or structure, list the Complex ID or API No.		20453		
Do you plan to use a subsea BOP or a surface BOP on a floating facility to conduct your proposed activities?							Yes	X	No
<b>WCD Info</b>	For wells, volume of uncontrolled blowout (Bbls/Day): 21,802			For structures, volume of all storage and pipelines (Bbls): 0		API Gravity of fluid		33°	
	<b>Surface Location</b>			<b>Bottom-Hole Location (For Wells)</b>		<b>Completion (For multiple completions, enter separate lines)</b>			
<b>Lease No.</b>	OCS-G 01372					OCS OCS			
<b>Area Name</b>	Breton Sound								
<b>Block No.</b>	55								
<b>Blockline Departures (in feet)</b>	N/S Departure: 2,302' FSL			N/S Departure:		N/S Departure		F __ L	
	E/W Departure: 1,875' FWL			E/W Departure:		N/S Departure		F __ L	
<b>Lambert X-Y coordinates</b>	X: 2,725,725			X:		X:		F __ L	
	Y: 280,382			Y:		Y:		F __ L	
<b>Latitude/ Longitude</b>	Latitude: 29° 25' 4.2276" N			Latitude:		Latitude		F __ L	
	Longitude: 89° 3' 13.6584" W			Longitude:		Longitude		F __ L	
Water Depth (Feet): 28'				MD (Feet):		TVD (Feet):		MD (Feet):	
Anchor Radius (if applicable) in feet: N/A								TVD (Feet):	
								TVD (Feet):	
<b>Anchor Locations for Drilling Rig or Construction Barge (If anchor radius supplied above, not necessary)</b>									
<b>Anchor Name or No.</b>	<b>Area</b>	<b>Block</b>	<b>X Coordinate</b>		<b>Y Coordinate</b>		<b>Length of Anchor Chain on Seafloor</b>		
N/A			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				

**OCS PLAN INFORMATION FORM (CONTINUED)**  
**Include one copy of this page for each proposed well/structure**

Proposed Well/Structure Location									
Well or Structure Name/Number (If renaming well or structure, reference previous name): FA010				Previously reviewed under an approved EP or DOCD?		X	Yes		No
Is this an existing well or structure?		X	Yes	No	If this is an existing well or structure, list the Complex ID or API No.		17-726-00249-03		
Do you plan to use a subsea BOP or a surface BOP on a floating facility to conduct your proposed activities?							Yes	X	No
<b>WCD Info</b>	For wells, volume of uncontrolled blowout (Bbls/Day): 21,802			For structures, volume of all storage and pipelines (Bbls): 0		API Gravity of fluid		33°	
	<b>Surface Location</b>			<b>Bottom-Hole Location (For Wells)</b>		<b>Completion (For multiple completions, enter separate lines)</b>			
<b>Lease No.</b>	OCS-G 01372			OCS-G 32246		OCS OCS			
<b>Area Name</b>	Breton Sound			Breton Sound					
<b>Block No.</b>	55			55					
<b>Blockline Departures (in feet)</b>	N/S Departure: 2,302' FSL			N/S Departure:		N/S Departure		F __ L	
	E/W Departure: 1,875' FWL			E/W Departure:		E/W Departure		F __ L	
<b>Lambert X-Y coordinates</b>	X: 2,725,725			X:		X:		F __ L	
	Y: 280,382			Y:		Y:		F __ L	
<b>Latitude/ Longitude</b>	Latitude: 29° 25' 4.2276" N			Latitude:		Latitude		F __ L	
	Longitude: 89° 3' 13.6584" W			Longitude:		Longitude		F __ L	
Water Depth (Feet): 30'				MD (Feet):		TVD (Feet):		MD (Feet):	
Anchor Radius (if applicable) in feet: N/A								TVD (Feet):	
								TVD (Feet):	
<b>Anchor Locations for Drilling Rig or Construction Barge (If anchor radius supplied above, not necessary)</b>									
<b>Anchor Name or No.</b>	<b>Area</b>	<b>Block</b>	<b>X Coordinate</b>		<b>Y Coordinate</b>		<b>Length of Anchor Chain on Seafloor</b>		
N/A			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				

**OCS PLAN INFORMATION FORM (CONTINUED)**  
**Include one copy of this page for each proposed well/structure**

Proposed Well/Structure Location									
Well or Structure Name/Number (If renaming well or structure, reference previous name): FA013				Previously reviewed under an approved EP or DOCD?		X	Yes		No
Is this an existing well or structure?		X	Yes	No	If this is an existing well or structure, list the Complex ID or API No.		17-726-40035-01		
Do you plan to use a subsea BOP or a surface BOP on a floating facility to conduct your proposed activities?							Yes	X	No
<b>WCD Info</b>	For wells, volume of uncontrolled blowout (Bbls/Day): 21,802			For structures, volume of all storage and pipelines (Bbls): 0		API Gravity of fluid		33°	
	<b>Surface Location</b>			<b>Bottom-Hole Location (For Wells)</b>		<b>Completion (For multiple completions, enter separate lines)</b>			
<b>Lease No.</b>	OCS-G 01372			OCS-G 01367		OCS OCS			
<b>Area Name</b>	Breton Sound			Main Pass					
<b>Block No.</b>	55			42					
<b>Blockline Departures (in feet)</b>	N/S Departure: 2,305' FSL			N/S Departure:		N/S Departure		F __ L	
	E/W Departure: 1,870' FWL			E/W Departure:		E/W Departure		F __ L	
<b>Lambert X-Y coordinates</b>	X: 2,725,720			X:		X:		X:	
	Y: 280,385			Y:		Y:		Y:	
<b>Latitude/ Longitude</b>	Latitude: 29° 25' 4.2564" N			Latitude:		Latitude		Latitude	
	Longitude: 89° 3' 13.7124" W			Longitude:		Longitude		Longitude	
Water Depth (Feet): 30'				MD (Feet):		TVD (Feet):		MD (Feet):	
Anchor Radius (if applicable) in feet: N/A								TVD (Feet):	
<b>Anchor Locations for Drilling Rig or Construction Barge (If anchor radius supplied above, not necessary)</b>									
<b>Anchor Name or No.</b>	<b>Area</b>	<b>Block</b>	<b>X Coordinate</b>		<b>Y Coordinate</b>		<b>Length of Anchor Chain on Seafloor</b>		
N/A			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				
			X:		Y:				

**OCS PLAN INFORMATION FORM (CONTINUED)**  
**Include one copy of this page for each proposed well/structure**

Proposed Well/Structure Location										
Well or Structure Name/Number (If renaming well or structure, reference previous name): FAB				Previously reviewed under an approved EP or DOCD?			Yes	X	No	
Is this an existing well or structure?		Yes	X	No	If this is an existing well or structure, list the Complex ID or API No.					
Do you plan to use a subsea BOP or a surface BOP on a floating facility to conduct your proposed activities?						Yes	X	No		
<b>WCD Info</b>	For wells, volume of uncontrolled blowout (Bbls/Day): 21,802			For structures, volume of all storage and pipelines (Bbls): 0		API Gravity of fluid		33°		
	<b>Surface Location</b>			<b>Bottom-Hole Location (For Wells)</b>			<b>Completion (For multiple completions, enter separate lines)</b>			
<b>Lease No.</b>	OCS-G 01372			OCS-G			OCS OCS			
<b>Area Name</b>	Breton Sound									
<b>Block No.</b>	55									
<b>Blockline Departures (in feet)</b>	N/S Departure: 2,299.98' FSL			N/S Departure:			N/S Departure F __ L			
	E/W Departure: 1,868.70' FWL			E/W Departure:			N/S Departure F __ L			
<b>Lambert X-Y coordinates</b>	X: 2,725,718.70			X:			E/W Departure F __ L			
	Y: 280,379.98			Y:			E/W Departure F __ L			
<b>Latitude/ Longitude</b>	Latitude: 29° 25' 04.2083" N			Latitude:			E/W Departure F __ L			
	Longitude: 89° 03' 13.7291" W			Longitude:			E/W Departure F __ L			
Water Depth (Feet): 28'				MD (Feet):		TVD (Feet):		MD (Feet):		TVD (Feet):
Anchor Radius (if applicable) in feet: N/A								MD (Feet):		TVD (Feet):
Anchor Locations for Drilling Rig or Construction Barge (If anchor radius supplied above, not necessary)										
Anchor Name or No.	Area	Block	X Coordinate		Y Coordinate		Length of Anchor Chain on Seafloor			
N/A			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					

**OCS PLAN INFORMATION FORM (CONTINUED)**  
**Include one copy of this page for each proposed well/structure**

Proposed Well/Structure Location										
Well or Structure Name/Number (If renaming well or structure, reference previous name): FAB1				Previously reviewed under an approved EP or DOCD?			Yes	X	No	
Is this an existing well or structure?		Yes	X	No	If this is an existing well or structure, list the Complex ID or API No.					
Do you plan to use a subsea BOP or a surface BOP on a floating facility to conduct your proposed activities?						Yes	X	No		
<b>WCD Info</b>	For wells, volume of uncontrolled blowout (Bbls/Day): 21,802			For structures, volume of all storage and pipelines (Bbls): 0			API Gravity of fluid		33°	
	<b>Surface Location</b>			<b>Bottom-Hole Location (For Wells)</b>			<b>Completion (For multiple completions, enter separate lines)</b>			
<b>Lease No.</b>	OCS-G 01372			OCS 00375			OCS OCS			
<b>Area Name</b>	Breton Sound			Main Pass						
<b>Block No.</b>	55			42						
<b>Blockline Departures (in feet)</b>	N/S Departure: 2,331.97' FSL			N/S Departure:			N/S Departure F __ L			
	E/W Departure: 1,888.66' FWL			E/W Departure:			N/S Departure F __ L			
<b>Lambert X-Y coordinates</b>	X: 2,725,738.66			X:			E/W Departure F __ L			
	Y: 280,411.97			Y:			E/W Departure F __ L			
<b>Latitude/ Longitude</b>	Latitude: 29° 25' 04.5210" N			Latitude:			E/W Departure F __ L			
	Longitude: 89° 03' 13.4963" W			Longitude:			E/W Departure F __ L			
Water Depth (Feet): 39'				MD (Feet):		TVD (Feet):		MD (Feet):		TVD (Feet):
Anchor Radius (if applicable) in feet: N/A								MD (Feet):		TVD (Feet):
Anchor Locations for Drilling Rig or Construction Barge (If anchor radius supplied above, not necessary)										
Anchor Name or No.	Area	Block	X Coordinate		Y Coordinate		Length of Anchor Chain on Seafloor			
N/A			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					

**OCS PLAN INFORMATION FORM (CONTINUED)**  
**Include one copy of this page for each proposed well/structure**

Proposed Well/Structure Location										
Well or Structure Name/Number (If renaming well or structure, reference previous name): FAB2				Previously reviewed under an approved EP or DOCD?			Yes	X	No	
Is this an existing well or structure?		Yes	X	No	If this is an existing well or structure, list the Complex ID or API No.					
Do you plan to use a subsea BOP or a surface BOP on a floating facility to conduct your proposed activities?						Yes	X	No		
<b>WCD Info</b>	For wells, volume of uncontrolled blowout (Bbls/Day): 21,802			For structures, volume of all storage and pipelines (Bbls): 0			API Gravity of fluid		33°	
	<b>Surface Location</b>			<b>Bottom-Hole Location (For Wells)</b>			<b>Completion (For multiple completions, enter separate lines)</b>			
<b>Lease No.</b>	OCS-G 01372			OCS-G 01452			OCS OCS			
<b>Area Name</b>	Breton Sound			Main Pass						
<b>Block No.</b>	55			43						
<b>Blockline Departures (in feet)</b>	N/S Departure: 2,325.58' FSL			N/S Departure:			N/S Departure		F _ L	
	E/W Departure: 1,876.51' FWL			E/W Departure:			E/W Departure		F _ L	
<b>Lambert X-Y coordinates</b>	X: 2,725,726.51			X:			X:		X:	
	Y: 280,405.58			Y:			Y:		Y:	
<b>Latitude/ Longitude</b>	Latitude: 29° 25' 04.4601" N			Latitude:			Latitude		Latitude	
	Longitude: 89° 03' 13.6351" W			Longitude:			Longitude		Longitude	
Water Depth (Feet): 39'				MD (Feet):		TVD (Feet):		MD (Feet):		TVD (Feet):
Anchor Radius (if applicable) in feet: N/A								MD (Feet):		TVD (Feet):
Anchor Locations for Drilling Rig or Construction Barge (If anchor radius supplied above, not necessary)										
Anchor Name or No.	Area	Block	X Coordinate		Y Coordinate		Length of Anchor Chain on Seafloor			
N/A			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					




**OCS PLAN INFORMATION FORM (CONTINUED)**  
**Include one copy of this page for each proposed well/structure**

Proposed Well/Structure Location										
Well or Structure Name/Number (If renaming well or structure, reference previous name): FAB3				Previously reviewed under an approved EP or DOCD?			Yes	X	No	
Is this an existing well or structure?		Yes	X	No	If this is an existing well or structure, list the Complex ID or API No.					
Do you plan to use a subsea BOP or a surface BOP on a floating facility to conduct your proposed activities?						Yes	X	No		
<b>WCD Info</b>	For wells, volume of uncontrolled blowout (Bbls/Day): 21,802			For structures, volume of all storage and pipelines (Bbls): 0			API Gravity of fluid		33°	
	<b>Surface Location</b>			<b>Bottom-Hole Location (For Wells)</b>			<b>Completion (For multiple completions, enter separate lines)</b>			
<b>Lease No.</b>	OCS-G 01372			OCS-G 01452			OCS OCS			
<b>Area Name</b>	Breton Sound			Main Pass						
<b>Block No.</b>	55			43						
<b>Blockline Departures (in feet)</b>	N/S Departure: 2,321.92' FSL			N/S Departure:			N/S Departure		F __ L	
	E/W Departure: 1,883.06' FWL			E/W Departure:			E/W Departure		F __ L	
<b>Lambert X-Y coordinates</b>	X: 2,725,733.06			X:			X:		X:	
	Y: 280,401.92			Y:			Y:		Y:	
<b>Latitude/ Longitude</b>	Latitude: 29° 25' 04.4226" N			Latitude:			Latitude		Latitude	
	Longitude: 89° 03' 13.5619" W			Longitude:			Longitude		Longitude	
Water Depth (Feet): 39'				MD (Feet):		TVD (Feet):		MD (Feet):		TVD (Feet):
Anchor Radius (if applicable) in feet: N/A								MD (Feet):		TVD (Feet):
Anchor Locations for Drilling Rig or Construction Barge (If anchor radius supplied above, not necessary)										
Anchor Name or No.	Area	Block	X Coordinate		Y Coordinate		Length of Anchor Chain on Seafloor			
N/A			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					

**OCS PLAN INFORMATION FORM (CONTINUED)**  
**Include one copy of this page for each proposed well/structure**

Proposed Well/Structure Location										
Well or Structure Name/Number (If renaming well or structure, reference previous name): FAB4				Previously reviewed under an approved EP or DOCD?			Yes	X	No	
Is this an existing well or structure?		Yes	X	No	If this is an existing well or structure, list the Complex ID or API No.					
Do you plan to use a subsea BOP or a surface BOP on a floating facility to conduct your proposed activities?						Yes	X	No		
<b>WCD Info</b>	For wells, volume of uncontrolled blowout (Bbls/Day): 21,802			For structures, volume of all storage and pipelines (Bbls): 0			API Gravity of fluid		33°	
	<b>Surface Location</b>			<b>Bottom-Hole Location (For Wells)</b>			<b>Completion (For multiple completions, enter separate lines)</b>			
<b>Lease No.</b>	OCS-G 01372			OCS-G 01372			OCS OCS			
<b>Area Name</b>	Breton Sound			Breton Sound						
<b>Block No.</b>	55			55						
<b>Blockline Departures (in feet)</b>	N/S Departure: 2,318.27' FSL			N/S Departure:			N/S Departure		F __ L	
	E/W Departure: 1,889.61' FWL			E/W Departure:			E/W Departure		F __ L	
<b>Lambert X-Y coordinates</b>	X: 2,725,739.61			X:			X:		X:	
	Y: 280,398.27			Y:			Y:		Y:	
<b>Latitude/ Longitude</b>	Latitude: 29° 25' 04.3852" N			Latitude:			Latitude		Latitude	
	Longitude: 89° 03' 13.4887" W			Longitude:			Longitude		Longitude	
Water Depth (Feet): 39'				MD (Feet):		TVD (Feet):		MD (Feet):		TVD (Feet):
Anchor Radius (if applicable) in feet: N/A								MD (Feet):		TVD (Feet):
Anchor Locations for Drilling Rig or Construction Barge (If anchor radius supplied above, not necessary)										
Anchor Name or No.	Area	Block	X Coordinate		Y Coordinate		Length of Anchor Chain on Seafloor			
N/A			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					
			X:		Y:					



PROPOSED LOCATIONS NAD27 LOUISIANA SOUTH							
LOCATION	CALLNS	CALLEW	X COORDINATE	Y COORDINATE	LATITUDE	LONGITUDE	WD
Structure "FAB"	2299.98' FSL	1868.70' FWL	2,725,718.70'	280,379.98'	29°25'04.2083"N	89°03'13.7291"W	28'
FAB1 Surf.	2331.97' FSL	1888.66' FWL	2,725,738.66'	280,411.97'	29°25'04.5210"N	89°03'13.4963"W	39'
FAB2 Surf.	2325.58' FSL	1876.51' FWL	2,725,726.51'	280,405.58'	29°25'04.4601"N	89°03'13.6351"W	39'
FAB3 Surf.	2321.92' FSL	1883.06' FWL	2,725,733.06'	280,401.92'	29°25'04.4226"N	89°03'13.5619"W	39'
FAB4 Surf.	2318.27' FSL	1889.61' FWL	2,725,739.61'	280,398.27'	29°25'04.3852"N	89°03'13.4887"W	39'

**PUBLIC INFORMATION**




**DEVELOPMENT OPERATIONS  
COORDINATION DOCUMENT**  
 OCS-G-01372 BRETON SOUND AREA BLOCK 55  
 OCS-00375 AND OCS-00375 MAIN PASS AREA BLOCK 42 AND 43  
 GULF OF MEXICO

Geodetic Datum: NAD27  
 Projection: LOUISIANA SOUTH  
 Grid Units: US SURVEY FEET



Job No.: 19010798	Date: 8/20/2019	Drwn: EA	Chart: 1 Of: 1
DWG File: 19010798_BS55-MP42-43_DOCX_FAB1-4_01372-00375-01452			8/20/2019

**BS55**  
OCS-G-01372  
Cantium



COGO Pt - XY LL LA-S-MOD				
Description	Northing	Easting	Latitude	Longitude
FAB 1	280,411.97'	2,725,738.66'	29°25'04.5210"N	89°03'13.4963"W
FAB 2	280,405.58'	2,725,726.51'	29°25'04.4601"N	89°03'13.6351"W
FAB 3	280,401.92'	2,725,733.06'	29°25'04.4227"N	89°03'13.5619"W



**LEGEND**

STRUCTURE	HAZARD
PLATFORM (damaged/salv.)	ANCH. PILE
WELL (damaged/salv.)	OBSTRUCTION
PIPELINE	USCG HAZARD
ACTIVE	AVOIDANCE
OUT OF SERV.	ANOMALY
ABANDONED	CONTACT
UN. CONST.	BUFFER
PROPOSED	MOORING
PROP REM.	ANCH. ROPE
REMOVED	PROP. ROPE
POSITION	ANCH. / PILE
FEATURE	ANCH. BUOY
VALVE	
HUB	
CROSSING	




**PROPOSED WELLS  
DETAIL**  
BLOCK 55  
BRETON SOUND AREA  
GULF OF MEXICO

Geodetic Datum: NAD27  
Projection: LOUISIANA SOUTH  
Grid Units: US SURVEY FEET




FUGRO USA MARINE, INC.  
6100 Hillcroft Ave.  
Houston, Texas 77081  
(713) 346-3700

Plot Date: 7/30/2019 DWG Filename: Z:\2019\CANTIUM\5194\WORKING DRAWINGS\5194-001.DWG



**ELEVATION**  
SCALE: 3/16" = 1'-0"




**KEY PLAN**  
SCALE: 3/16" = 1'-0"

LIST OF COMPONENTS	
ITEMS	TOTAL WEIGHT (TONS)
SERVICE DECK	29.1
CAISSON	56.9
STAIR	0.5
<b>TOTAL</b>	<b>86.5</b>

**NOTES:**  
 1. ALL MATERIAL SHOWN ON THIS DRAWING IS **NEW** UNLESS NOTED.  
 2. FOR GENERAL NOTES SEE DRAWING NO. 101 AND 201.



APP'D.	CHK'D.	DRAFT	DATE	REVISION
SS	JR	KN	6/24/19	APPROVED FOR CONSTRUCTION
SS	JR	KN	6/20/19	ISSUED FOR APPROVAL



**CANTIUM**  
TECHNICAL ENGINEERING CONSULTANTS  
GRETNA, LOUISIANA TX. REG. NO. 9032

APPROVED	DATE	TITLE
SS	6/3/19	CAISSON WELL PROTECTOR BRETON SOUND BLOCK 55-FAB 28'-0" W.D.
DESIGN	MS	6/3/19
CHECK	JR	6/20/19
DRAFT	KN	6/3/19
CLIENT	CANTIUM LLC	JOB NO. 5194 DWG. NO. 001

## ATTACHMENT 1 - C



## Confirmation

---

Your payment has been submitted to the designated government agency through Pay.gov and the details are below. Please note that this is just a confirmation of transaction submission. To confirm that the payment processed as expected, you may refer to your bank statement on the scheduled payment date. If you have any questions or wish to cancel this payment, you will need to contact the agency you paid at your earliest convenience.

### Tracking Information

Pay.gov Tracking ID: 26IHADTA

Agency Tracking ID: 75784086515

Form Name: BOEM Development Operations Coordination Document or DPP

Application Name: BOEM Development/DOCD Plan - BD

### Payment Information

Payment Type: Bank account (ACH)

Payment Amount: \$12,714.00

Transaction Date: 07/01/2019 04:11:00 PM EDT

Payment Date: 07/02/2019

Region: Gulf of Mexico

Contact: SHERI MERRELL 5042563602

Company Name/No: Cantium, LLC, 03481

Lease Number(s): 01372, 00375, 01452, ,

Area-Block: Breton Sound BS, 55: Main Pass MP, 42: Main Pass MP, 43: , : ,

Type-Wells: Supplemental Plan, 3

**Account Information**

Account Holder Name: Cantium, LLC

Routing Number: 065400137

Account Number: \*\*\*\*\*9230



## Confirmation

---

Your payment has been submitted to the designated government agency through Pay.gov and the details are below. Please note that this is just a confirmation of transaction submission. To confirm that the payment processed as expected, you may refer to your bank statement on the scheduled payment date. If you have any questions or wish to cancel this payment, you will need to contact the agency you paid at your earliest convenience.

### Tracking Information

Pay.gov Tracking ID: 26JMKIBU

Agency Tracking ID: 75823257732

Form Name: BOEM Development Operations Coordination Document or DPP

Application Name: BOEM Development/DOCD Plan - BD

### Payment Information

Payment Type: Bank account (ACH)

Payment Amount: \$4,238.00

Transaction Date: 08/23/2019 11:14:25 AM EDT

Payment Date: 08/26/2019

Region: Gulf of Mexico

Contact: Sheri Merrell 5042563602

Company Name/No: Cantium, LLC, 03481

Lease Number(s): 00375, 01452, , ,



Area-Block: Breton Sound BS, 55: Main Pass MP, 42: Main Pass MP, 43: , ,

Type-Wells: Supplemental Plan, 1

**Account Information**

Account Holder Name: Cantium, LLC

Routing Number: 065400137

Account Number: \*\*\*\*\*9230

## SECTION 2 GENERAL INFORMATION

### 2.1 APPLICATIONS AND PERMITS

The table below provides the additional applications to be filed covering operations proposed in this DOCD.

Application/Permit	Issuing Agency	Status
APD	BSEE	To Be Submitted
APM	BSEE	To Be Submitted
Structure Application	BSEE	To Be Submitted

### 2.2 DRILLING FLUIDS

The table below provides the types and estimated volumes of the drilling fluids Cantium plans to use to drill the proposed well.

Type of Drilling Fluid	Estimated Volume of Drilling Fluid to be Used per Well (bbl)
Water-based (seawater, freshwater, barite)	5,000
Oil-based (diesel, mineral oil)	0
Synthetic-based (internal olefin, ester)	11,000

### 2.3 PRODUCTION

Proprietary Information

### 2.4 OIL CHARACTERISTICS

Proprietary Information

### 2.5 NEW OR UNUSUAL TECHNOLOGY

Proprietary Information

### 2.6 BONDING STATEMENT

The bond requirements for the activities and facilities proposed in this DOCD are satisfied by an area-wide bond, furnished and maintained according to 30 CFR 556.900 (a) and 30 CFR 556.901 (a) and (b) and NTL No. 2015-BOEM-N04, "General Financial Assurance"; and additional security under 30 CFR 556.901(d) – (f) and NTL No. 2016—BOEM-N01, "Requiring Additional Security" as required by BOEM.

## 2.7 OIL SPILL FINANCIAL RESPONSIBILITY (OSFR)

Cantium, LLC (Company No. 03481) has demonstrated oil spill financial responsibility for the facilities proposed in this DOCD according to 30 CFR Part 553.15 (a); and NTL No. 2008-N05, "Guidelines for Oil Spill Financial Responsibility for Covered Facilities".

## 2.8 DEEPWATER WELL CONTROL STATEMENT

Operations proposed in this plan are located in water depths less than 300 meters (984 feet); therefore, a deepwater well control statement is not provided.

## 2.9 SUSPENSION OF PRODUCTION

Cantium does not anticipate filing any requests for Suspension of Production to hold the leases or unit addressed in this DOCD in active status.

## 2.10 BLOWOUT SCENARIO AND WORST CASE DISCHARGE CALCULATIONS

In accordance with the requirements outlined in NTL No. 2015-BOEM-N01, "Information Requirements for Exploration Plans, Development and Production Plans, and Development Operations Coordination Documents on the OCS for Worst Case Discharge and Blowout Scenarios," the following information is provided:

The Worst Case Discharge is defined as an uncontrolled blowout through the drilling string during drilling operations.

**Estimated initial flow rate:** The calculated Worst Case Discharge estimate for Breton Sound Block 55 / Main Pass Block 42 Well No. FAB1 is 21,802 bbl of crude.

**Maximum duration/total volume that could occur if the Breton Sound Block 55 / Main Pass Block 42 Well No. FAB1 sustained a blowout:**

Scenario	Maximum Discharge Rate (bbl/day)	Discharge Duration (days)	Total Volume Crude (bbl)
Relief Well	21,802	60	1,308,120

**Potential of wellbore to bridge over during a blowout:** Due to the unconsolidated nature of the sand quality of the proposed target reservoir, the potential for the well to bridge over is very high within the first 5-10 days of a loss of control incident. The planned casing program exits existing casing at a depth where fracture gradient is high enough to hold in the event the wellbore has been fully evacuated with gas. Drilling techniques would likely experience an underground blowout as the path of least resistance preceded by bridging in the wellbore.

**Likelihood for surface intervention to stop blowout:** Most successful well kill operations are conducted via surface intervention by trained well control specialists. In the event of an actual blowout, intervention at the surface will be guided by well control specialists from Wild Well Control. The jack-up rig style offers good access to surface well control equipment for surface intervention.

## Relief Well

**Rig type capable of drilling relief well at water depth and to TD:** The type of rig necessary to drill in water depths up to 39' would be either a mat jack-up or an independent leg rig. There are approximately 5 units of this type available in the Gulf of Mexico fleet. A relief well rig can be placed a safe distance from the affected rig and still reach intercept depths needed. Rigs we can use to drill a relief well are WFD #300, WFD #350, Enterprise #264, Ensco #68, and Spartan #202.

**Rig package constraints:** Some rigs may be restricted during hurricane season, but there are several rigs available that are not restricted.

### Time to acquire rig, move onsite and drill relief well:

Activity	Duration (days)
Assess the situation and obtain the optimum MODU; secure well at current location of MODU	15
Mobilization time to relief well location	5
Drill the relief well, intersect and kill the well	40
Total anticipated time	60

**Statement whether possibility of using nearby platform was considered:** Yes, if a mat rig was selected, the rig would position on the F platform which is approximately 5000' away. To reduce drill time with an easier directional approach, an open water location 500' to 1000' is another option, especially if using an independent-leg type rig.

**Other measures to enhance ability to prevent a blowout:** The fracture gradient of the window shoe is designed to be strong enough to allow for shut-in of the wellbore with 80% gas evacuation. In Main Pass, any open hole wellbore influx would also include contributions from significant, exposed water sands, so in a blowout scenario, there would always be a large volume of fluids associated with the flow stream. Cantium will adhere to and conduct all operations in compliance with all regulations. This would include, but not be limited to:

- Sufficient mud weight margin can be maintained without mud losses.
- Test and certify BOPs with proper working pressure.
- Maintain enough barite on location to weight up the mud system 0.5 ppg.
- Properly test TIW and BOP on rig floor.
- Monitor trip speeds to minimize surge and swab pressures.
- Check well for flow regularly especially following drilling breaks.
- Rig up and function test gas detectors properly.
- Earnestly conduct well control drills with each crew.
- Thoroughly review offset information to identify drilling hazards.

Drilling information will be available for real-time display and reviewed by office engineers and rig superintendents via a company like OFI. Drilling information will be available for monitoring

24/7 with geoscience team for accurate pore pressure analysis via OFI along with real time Baker LWD transmission.

**Measures to reduce the likelihood of a blowout:**

- Perform offset-well history review. Most wells are drilled in known fields with established pressure profiles.
- Create proper mud design and maintain MW to control well as per the offset information.
- Design and maintain in proper functioning order the atmospheric degasser.
- Maintain stuck pipe spotting material on location.
- Maintain enough LCM material on location to mix two pills.
- Monitor pressures while making preparations to circulate the invading fluids out of the wellbore and regain hydrostatic pressure control of the formation pressure, should the well need to be shut it.
- Run cement bond logs where applicable.
- Make routine short trips when warranted.
- Circulate bottoms up frequently.
- Run centralizers by normally accepted practices where applicable.
- Model cement jobs and drilling fluid hydraulics for rate and ecd effects.

**Measures to enhance ability to conduct effective and early intervention in event of a blowout:**

- Minimize the impact of an event by having well trained personnel at the well site.
- Be sure drillers understand it is always acceptable to shut-in a well to evaluate well conditions at any time.
- Make initial contact with surface intervention specialist.
- Perform hazard assessment and operations assessment to establish path forward.
- Set up firefighting equipment of vessels.
- Begin firewater application to cool the area or to prevent ignition while working in proximity to flow.
- Clear debris and move onto the rig.
- Cut off damaged wellhead and BOPs.
- Install new wellhead.
- Install diverter and capping stack.
- Rig up snubbing unit.
- Snub in and kill well.

**Arrangements for drilling relief wells:**

- Maintain awareness of the location of other rigs working in the Gulf Shelf.
- Build relations with other operators in the Shelf, like Arena, Cox, and Energy XXI who also support an active drilling program.
- The company that is providing the rig for the project has 1 additional rig at our call with a second expected in fourth quarter 2018.

- Other shelf operators understand we would seek the most readily and capable rig to respond and would work with other Operators as needed to make them available.
- The type of rig necessary to drill in water depths of 39' is either an independent leg jack-up rig or mat jack-up.
- There are approximately 5 rigs working on the shelf that are available in the Gulf of Mexico fleet.

**Any other measures:** N/A

## **SECTION 3 GEOLOGICAL AND GEOPHYSICAL INFORMATION**

### **3.1 GEOLOGICAL DESCRIPTION**

Proprietary Information

### **3.2 STRUCTURE CONTOUR MAPS**

Proprietary Information

### **3.3 INTERPRETED SEISMIC LINES**

Proprietary Information

### **3.4 GEOLOGICAL STRUCTURE CROSS-SECTIONS**

Proprietary Information

### **3.5 SHALLOW HAZARDS REPORT**

The proposed operations will be conducted from a previously approved surface location; therefore, in accordance with NTL No. 2008-G05, "Shallow Hazards Program," a shallow hazards report is not provided.

### **3.6 SHALLOW HAZARDS ASSESSMENT**

The proposed operations will be conducted from a previously approved surface location; therefore, in accordance with NTL No. 2008-G05, "Shallow Hazards Program," a site-specific shallow hazards assessment is not provided.

### **3.7 HIGH-RESOLUTION SEISMIC LINES**

Proprietary Information

### **3.8 STRATIGRAPHIC COLUMN**

Proprietary Information

### **3.9 TIME VS DEPTH TABLES**

Proprietary Information

## **SECTION 4 HYDROGEN SULFIDE INFORMATION**

### **4.1 CONCENTRATION**

Cantium anticipates encountering 0 ppm H<sub>2</sub>S during the proposed operations.

### **4.2 CLASSIFICATION**

In accordance with Title 30 CFR 250.490(c), Cantium requests that the area of proposed operations be classified by the BOEM as H<sub>2</sub>S absent.

### **4.3 H<sub>2</sub>S CONTINGENCY PLAN**

An H<sub>2</sub>S Contingency Plan is not required for the activities proposed in this plan.

### **4.4 MODELING REPORT**

Modeling reports are not required for the activities proposed in this plan.



## **SECTION 5 MINERAL RESOURCE CONSERVATION INFORMATION**

### **5.1 TECHNOLOGY & RESERVOIR ENGINEERING PRACTICES AND PROCEDURES**

Proprietary Information

### **5.2 TECHNOLOGY AND RECOVERY PRACTICES AND PROCEDURES**

Proprietary Information

### **5.3 RESERVOIR DEVELOPMENT**

Proprietary Information

## **SECTION 6**

### **BIOLOGICAL, PHYSICAL AND SOCIOECONOMIC INFORMATION**

#### **6.1 DEEPWATER BENTHIC COMMUNITIES**

Activities proposed in this DOCD are in water depths less than 300 meters (984 feet); therefore, information as outlined in Attachment A of NTL No. 2009-G40, "Deepwater Benthic Communities," is not provided.

#### **6.2 TOPOGRAPHIC FEATURES (BANKS)**

Activities proposed in this DOCD do not fall within 305 meters (1000 feet) of a topographic "No Activity Zone;" therefore, no map is required per NTL No. 2009-G39, "Biologically Sensitive Underwater Features and Areas."

#### **6.3 TOPOGRAPHIC FEATURES STATEMENT (SHUNTING)**

Activities proposed under this DOCD will be conducted outside all Topographic Feature Protective Zones; therefore, shunting of drill cuttings and drilling fluids is not required per NTL No. 2009-G39, "Biologically Sensitive Underwater Features and Areas."

#### **6.4 LIVE-BOTTOMS (PINNACLE TREND FEATURES)**

Breton Sound Block 55 is not located within 61 meters (200 feet) of any pinnacle trend feature; therefore, a separate bathymetric map is not required per NTL No. 2009-G39, "Biologically Sensitive Underwater Features and Areas."

#### **6.5 LIVE BOTTOMS (LOW RELIEF)**

Breton Sound Block 55 is not located within 30 meters (100 feet) of any live bottom (low relief) feature with vertical relief equal to or greater than 8 feet; therefore, live bottom (low relief) maps are not required per NTL No. 2009-G39, "Biologically Sensitive Underwater Features and Areas."

#### **6.6 POTENTIALLY SENSITIVE BIOLOGICAL FEATURES**

Breton Sound Block 55 is not located within 30 meters (100 feet) of potentially sensitive biological features. In accordance with NTL No. 2009-G39, "Biologically Sensitive Underwater Features and Areas," biologically sensitive area maps are not required.

#### **6.7 THREATENED AND ENDANGERED SPECIES, CRITICAL HABITAT AND MARINE MAMMAL INFORMATION**

The federally listed endangered and threatened species potentially occurring in the lease area and along the Gulf Coast are provided in the table below.

Species	Scientific Name	Status	Potential Presence		Critical Habitat Designated in the Gulf of Mexico
			Lease Area	Coastal	
<b>Marine Mammals</b>					
Manatee, West Indian	<i>Trichechus manatus latirostris</i>	E	--	X	Florida (peninsular)
Whale, Blue	<i>Balaenoptera masculus</i>	E	X	--	None
Whale, Bryde's	<i>Balaenoptera edeni</i>	E	X	--	None
Whale, Finback	<i>Balaenoptera physalus</i>	E	X	--	None
Whale, Humpback	<i>Megaptera novaeangliae</i>	E	X	--	None
Whale, North Atlantic Right	<i>Eubalaena glacialis</i>	E	X	--	None
Whale, Sei	<i>Balaenoptera borealis</i>	E	X	--	None
Whale, Sperm	<i>Physeter catodon</i> (= <i>macrocephalus</i> )	E	X	--	None
<b>Terrestrial Mammals</b>					
Mouse, Beach (Alabama, Choctawatchee, Perdido Key, St. Andrew)	<i>Peromyscus polionotus</i>	E	-	X	Alabama, Florida (panhandle) beaches
<b>Birds</b>					
Plover, Piping	<i>Charadrius melodus</i>	T	-	X	Coastal Texas, Louisiana, Mississippi, Alabama and Florida (panhandle)
Crane, Whooping	<i>Grus Americana</i>	E	-	X	Coastal Texas
<b>Reptiles</b>					
Sea Turtle, Green	<i>Chelonia mydas</i>	T	X	X	None
Sea Turtle, Hawksbill	<i>Eretmochelys imbricata</i>	E	X	X	None
Sea Turtle, Kemp's Ridley	<i>Lepidochelys kempli</i>	E	X	X	None
Sea Turtle, Leatherback	<i>Dermochelys coriacea</i>	E	X	X	None
Sea Turtle, Loggerhead	<i>Caretta caretta</i>	T	X	X	Texas, Louisiana, Mississippi, Alabama, Florida
<b>Fish</b>					
Sturgeon, Gulf	<i>Acipenser oxyrinchus</i> (= <i>oxyrhynchus</i> ) <i>desotoi</i>	T	X	X	Coastal Louisiana, Mississippi, Alabama and Florida (panhandle)
<b>Corals</b>					
Coral, Elkhorn	<i>Acopora palmate</i>	T	-	X	Florida Keys and Dry Tortugas
Coral, Staghorn	<i>Acopora cervicornis</i>	T	-	X	Florida

Abbreviations: E = Endangered; T = Threatened

\* The Blue Fin, Humpback, North Atlantic Right, and Sei Whales are rare or extralimital in the Gulf of Mexico and are unlikely to be present in the lease area.

## **6.8 ARCHAEOLOGICAL REPORT**

The proposed operations will be conducted from a previously approved surface location; therefore, in accordance with NTL No. 2005-G07, "Archaeological Resource Surveys and Reports," and NTL No. 2011-JOINT-G01, "Revisions to the List of OCS Lease Blocks Requiring Archaeological Resource Surveys and Reports," an archaeological resource survey report is not provided.

## **6.9 AIR AND WATER QUALITY INFORMATION**

Air and water quality information is not required to be included in this plan per NTL No. 2008-G04, "Information Requirements for Exploration Plans and Development Operations Coordination Documents."

## **6.10 SOCIOECONOMIC INFORMATION**

Socioeconomic information is not required to be included in this plan per NTL No. 2008-G04, "Information Requirements for Exploration Plans and Development Operations Coordination Documents."

## SECTION 7 WASTES AND DISCHARGES INFORMATION

### 7.1 PROJECTED GENERATED WASTES

“Wastes You Will Generate, Treat and Downhole Dispose or Discharge to the Gulf of Mexico” is included as **Attachment 7-A**.

### 7.2 MODELING REPORT

Modeling reports are not required for the activities proposed in this plan.

# ATTACHMENT 7-A WASTE ESTIMATED TO BE GENERATED, TREATED AND/OR DOWNHOLE DISPOSED OR DISCHARGED TO THE GOM

Please specify if the amount reported is a total or per well amount and be sure to include appropriate units.

Projected generated waste			Projected ocean discharges		Projected Downhole Disposal
Type of Waste	Composition	Projected Amount	Discharge rate	Discharge Method	Answer yes or no
<b>Will drilling occur ? If yes, you should list muds and cuttings</b>					
Water-based drilling fluid	Spud Mud, Low-solids non dispersed water-based	10,000 bbl/well	24,000 bbls/day/well	discharged overboard	no
Cuttings wetted with water-based fluid	Cuttings generated while using water-based fluid	3,400 bbls/well	680 bbls/day/well	discharged overboard	no
Synthetic based drilling fluid	Synthetic based drilling fluid	11,000 bbls/well	NA	shipped to shore in below deck storage tanks and recycled	no
Cuttings wetted with synthetic-based fluid	Cuttings generated while using synthetic based fluids	8,100 bbls/well	350 bbls/day/well	discharged overboard	no
<b>Will humans be there? If yes, expect conventional waste</b>					
Domestic waste	Grey water from living quarters	30,000 bbls/well	10 bbls/hr/well	discharged overboard	no
Sanitary waste	Black water from living quarters	3,000 bbls/well	1 bbl/hr/well	treated and discharged overboard	no
<b>Is there a deck? If yes, there will be Deck Drainage</b>					
Deck Drainage	Rain	15,000 bbls/well	100 bbls/hr/well	discharged overboard	no
<b>Will you conduct well treatment, completion, or workover?</b>					
Well treatment fluids	NA				
Well completion fluids	NA				
Workover fluids	NA				
<b>Miscellaneous discharges. If yes, only fill in those associated with your activity.</b>					
Desalinization unit discharge	Super Saturated Seawater	44,000 bbl/well	15 bbls/hr/well	discharged overboard	no
Blowout prevent fluid	water based hydraulic fluid	750 bbl/well	0.25 bbls/hr/well	discharged overboard	no
Ballast water	Potable water	10,000 bbl/well	1,000 bbls/hr/well	discharged overboard	no
Bilge water	Seawater	10,000 bbls/well	1000 bbls/hr/well	discharged overboard	no
Excess cement at seafloor	Class H Cement	500 bbls/well	10 bbls/hr/well	discharged overboard	no
Fire water	Seawater	12,500 bbls/well	0.25 bbls/hr/well	discharged overboard	no
Cooling water	Seawater	300,000 bbls/well	100 bbls/hr/well	discharged overboard	no
<b>Will you produce hydrocarbons? If yes fill in for produced water.</b>					
Produced water	NA				
<b>Please enter individual or general to indicate which type of NPDES permit you will be covered by?</b>			General (GMG290615)		
NOTE: If you will not have a type of waste for the activity being applied for, enter NA for all columns in the row.			NOTE: All discharged wastes should comply with the requirements of the NPDES permit.		

## SECTION 8 AIR EMISSIONS INFORMATION

### 8.1 EMISSIONS WORKSHEETS AND SCREENING QUESTIONS

Screen Questions for DOCD's	Yes	No
Is any calculated Complex Total (CT) Emission amount (tons) associated with your proposed development activities more than 90% of the amounts calculated using the following formulas: $CT = 3400D^{2/3}$ for CO, and $CT = 33.3D$ for the other air pollutants (where D = distance to shore in miles)?		X
Do your emission calculations include any emission reduction measures or modified emission factors?		X
Does or will the facility complex associated with your proposed development and production activities process production from eight or more wells?		X
Do you expect to encounter H <sub>2</sub> S at concentrations greater than 20 parts per million (ppm)?		X
Do you propose to flare or vent natural gas for more than 48 continuous hours from any proposed well?		X
Do you propose to burn produced hydrocarbon liquids?		X
Are your proposed development and production activities located within 25 miles (40 kilometers) from shore?	X	
Are your proposed development and production activities located within 124 miles (200 kilometers) of the Breton Wilderness Area?	X	

### 8.2 SUMMARY INFORMATION

There are no existing facilities or activities co-located with the currently proposed activities; therefore, the Complex Total Emissions are the same as the Plan Emissions. Included as **Attachment 8-A** are Air Emission Worksheets showing the emissions calculations for the activities.

This information was calculated by: Dena Rodriguez  
(281) 578-3388  
[dena.rodriquez@jccteam.com](mailto:dena.rodriquez@jccteam.com)

Air emissions were calculated using historical actual fuel usage for the Enterprise 264 with a 25% safety factor added.

## DOCD AIR QUALITY SCREENING CHECKLIST

OMB Control No. 1010-0151  
OMB Approval Expires: 06/30/2021

COMPANY	Cantium, LLC
AREA	Breton Sound
BLOCK	55
LEASE	OCS-G 01372
PLATFORM	FA, FAB
WELL	FA010, FA013, FAB1, FAB2, FAB3, FAB4
COMPANY CONTACT	Dena Rodriguez
TELEPHONE NO.	281-578-3388
REMARKS	Drill, complete, test and place three wells on production, drill and complete a dumpflood well; utilizing Enterprise 264 or equivalent jackup MODU; Set FAB structure; install LT pipeline; Enterprise 264 jackup historical fuel usage used; no production equipment on structures; Emissions also provide for future operations on Wells FA010, FA013, FAB1, FAB2, FAB3, FAB4 including contingency drilling days each year for maintenance, workovers, recompletions, interventions and abandonment activities

LEASE TERM PIPELINE CONSTRUCTION INFORMATION:		
YEAR	NUMBER OF PIPELINES	TOTAL NUMBER OF CONSTRUCTION DAYS
2019	1	8 - Installation of Riser and Spools for Pipeline
2020	1	4 - Complete Installation of Pipeline
2021		
2022		
2023		
2024		
2025		
2026		
2027		
2028		
2029		



### AIR EMISSIONS COMPUTATION FACTORS

Fuel Usage Conversion Factors	Natural Gas Turbines		Natural Gas Engines		Diesel Recip. Engine		REF.	DATE
	SCF/hp-hr	9.524	SCF/hp-hr	7.143	GAL/hp-hr	0.0483	AP42 3.2-1	4/76 & 8/84

Equipment/Emission Factors	units	PM	SOx	NOx	VOC	CO	REF.	DATE
NG Turbines	gms/hp-hr		0.00247	1.3	0.01	0.83	AP42 3.2-1& 3.1-1	10/96
NG 2-cycle lean	gms/hp-hr		0.00185	10.9	0.43	1.5	AP42 3.2-1	10/96
NG 4-cycle lean	gms/hp-hr		0.00185	11.8	0.72	1.6	AP42 3.2-1	10/96
NG 4-cycle rich	gms/hp-hr		0.00185	10	0.14	8.6	AP42 3.2-1	10/96
Diesel Recip. < 600 hp.	gms/hp-hr	1	0.1835	14	1.12	3.03	AP42 3.3-1	10/96
Diesel Recip. > 600 hp.	gms/hp-hr	0.32	0.1835	11	0.33	2.4	AP42 3.4-1	10/96
Diesel Boiler	lbs/bbl	0.084	0.3025	0.84	0.008	0.21	AP42 1.3-12,14	9/98
NG Heaters/Boilers/Burners	lbs/mmscf	7.6	0.593	100	5.5	84	AP42 1.4-1, 14-2, & 14	7/98
NG Flares	lbs/mmscf		0.593	71.4	60.3	388.5	AP42 11.5-1	9/91
Liquid Flaring	lbs/bbl	0.42	6.83	2	0.01	0.21	AP42 1.3-1 & 1.3-3	9/98
Tank Vapors	lbs/bbl				0.03		E&P Forum	1/93
Fugitives	lbs/hr/comp.				0.0005		API Study	12/93
Glycol Dehydrator Vent	lbs/mmscf				6.6		La. DEQ	1991
Gas Venting	lbs/scf				0.0034			

Sulphur Content Source	Value	Units
Fuel Gas	3.33	ppm
Diesel Fuel	0.05	% weight
Produced Gas( Flares)	3.33	ppm
Produced Oil (Liquid Flaring)	1	% weight

**AIR EMISSIONS CALCULATIONS - FIRST YEAR**

COMPANY	AREA	BLOCK	LEASE	PLATFORM	WELL		CONTACT	PHONE	REMARKS								
Cantium, LLC	Breton Sound	55	OCS-G 01372	FA, FAB	FA010, FA013, FAB1, FAB2, FAB3, FAB4		Dena Rodriguez	281-578-3388	Drill, complete, test and place three wells on production, drill and complete a dumpflood well, utili								
OPERATIONS	EQUIPMENT	RATING	MAX. FUEL	ACT. FUEL	RUN TIME		MAXIMUM POUNDS PER HOUR					ESTIMATED TONS					
	Diesel Engines	HP	GAL/HR	GAL/D													
	Nat. Gas Engines	HP	SCF/HR	SCF/D													
	Burners	MMBTU/HR	SCF/HR	SCF/D	HR/D	D/YR	PM	SOx	NOx	VOC	CO	PM	SOx	NOx	VOC	CO	
DRILLING Enterprise 264 or equivalent jackup	PRIME MOVER>600hp diesel	6905	333.5115	1964.00	24	30	4.87	2.79	167.30	5.02	36.50	0.43	0.25	14.78	0.44	3.22	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	BURNER diesel	0			0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	AUXILIARY EQUIP<600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(crew)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	2065	99.7395	2393.75	10	30	1.46	0.83	50.03	1.50	10.92	0.22	0.13	7.50	0.23	1.64	
	VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
VESSELS>600hp diesel(tugs)	8400	405.72	9737.28	10	2	5.92	3.40	203.52	6.11	44.41	0.06	0.03	2.04	0.06	0.44		
PIPELINE INSTALLATION	PIPELINE LAY BARGE diesel	3200	154.56	3709.44	24	8	2.26	1.29	77.53	2.33	16.92	0.22	0.12	7.44	0.22	1.62	
	SUPPORT VESSEL diesel (2)	3000	144.9	3477.60	24	8	2.11	1.21	72.69	2.18	15.86	0.20	0.12	6.98	0.21	1.52	
	PIPELINE BURY BARGE diesel	4600	222.18	5332.32	24	8	3.24	1.86	111.45	3.34	24.32	0.31	0.18	10.70	0.32	2.33	
	SUPPORT VESSEL diesel (2)	3000	144.9	3477.60	24	8	2.11	1.21	72.69	2.18	15.86	0.20	0.12	6.98	0.21	1.52	
	VESSELS>600hp diesel(crew)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
FACILITY INSTALLATION	DERRICK BARGE diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	MATERIAL TUG diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(lift boat)	2000	96.6	2318.40	24	13	1.41	0.81	48.46	1.45	10.57	0.22	0.13	7.56	0.23	1.65	
	VESSELS>600hp diesel(utilty)	1500	72.45	1738.80	24	13	1.06	0.61	36.34	1.09	7.93	0.16	0.09	5.67	0.17	1.24	
PRODUCTION	RECIP.<600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	RECIP.>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	SUPPORT VESSEL diesel	2065	99.7395	2393.75	10	96	1.46	0.83	50.03	1.50	10.92	0.70	0.40	24.02	0.72	5.24	
	TURBINE nat gas	0	0	0.00	0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	RECIP.2 cycle lean nat gas	0	0	0.00	0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	RECIP.4 cycle lean nat gas	0	0	0.00	0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	RECIP.4 cycle rich nat gas	0	0	0.00	0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	BURNER nat gas	0	0.00	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	MISC.	BPD	SCF/HR	COUNT													
	TANK- FLARE- PROCESS VENT- FUGITIVES- GLYCOL STILL VENT-	0	0	0	0	0	0	0	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00
DRILLING WELL TEST	OIL BURN	0			0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	GAS FLARE		0		0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
<b>2019 YEAR TOTAL</b>							<b>25.89</b>	<b>14.85</b>	<b>890.06</b>	<b>26.95</b>	<b>194.19</b>	<b>2.72</b>	<b>1.56</b>	<b>93.66</b>	<b>3.90</b>	<b>20.44</b>	
<b>EXEMPTION CALCULATION</b>	<b>DISTANCE FROM LAND IN MILES</b>											<b>289.71</b>	<b>289.71</b>	<b>289.71</b>	<b>289.71</b>	<b>14382.19</b>	
	8.7																

AIR EMISSIONS CALCULATIONS - SECOND YEAR

COMPANY	AREA	BLOCK	LEASE	PLATFORM	WELL	CONTACT	PHONE	REMARKS									
Cantium, LLC	Breton Sound	55	OCS-G 01372	FA, FAB	FA010, FA013, FAB1, FAB2, FAB3, FAB4	Dena Rodriguez	281-578-3388	Drill, complete, test and place three wells on production, drill and complete a dumpflood well; utili									
OPERATIONS	EQUIPMENT	RATING	MAX. FUEL	ACT. FUEL	RUN TIME		MAXIMUM POUNDS PER HOUR					ESTIMATED TONS					
		HP	GAL/HR	GAL/D	HR/D	D/YR	PM	SOx	NOx	VOC	CO	PM	SOx	NOx	VOC	CO	
	Diesel Engines		HP	GAL/HR	GAL/D												
	Nat. Gas Engines		HP	SCF/HR	SCF/D												
Burners		MMBTU/HR	SCF/HR	SCF/D	HR/D	D/YR	PM	SOx	NOx	VOC	CO	PM	SOx	NOx	VOC	CO	
DRILLING	PRIME MOVER>600hp diesel	6905	333.5115	1964.00	24	185	4.87	2.79	167.30	5.02	36.50	2.65	1.52	91.13	2.73	19.88	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	BURNER diesel	0			0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	AUXILIARY EQUIP<600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(crew)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	2065	99.7395	2393.75	10	185	1.46	0.83	50.03	1.50	10.92	1.35	0.77	46.28	1.39	10.10	
	VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
VESSELS>600hp diesel(tugs)	8400	405.72	9737.28	10	2	5.92	3.40	203.52	6.11	44.41	0.06	0.03	2.04	0.06	0.44		
PIPELINE INSTALLATION	PIPELINE LAY BARGE diesel	3200	154.56	3709.44	24	4	2.26	1.29	77.53	2.33	16.92	0.11	0.06	3.72	0.11	0.81	
	SUPPORT VESSEL diesel (2)	3000	144.9	3477.60	24	4	2.11	1.21	72.69	2.18	15.86	0.10	0.06	3.49	0.10	0.76	
	PIPELINE BURY BARGE diesel	4600	222.18	5332.32	24	4	3.24	1.86	111.45	3.34	24.32	0.16	0.09	5.35	0.16	1.17	
	SUPPORT VESSEL diesel (2)	3000	144.9	3477.60	24	4	2.11	1.21	72.69	2.18	15.86	0.10	0.06	3.49	0.10	0.76	
	VESSELS>600hp diesel(crew)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
FACILITY INSTALLATION	DERRICK BARGE diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	MATERIAL TUG diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(crew)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
PRODUCTION	RECIP.<600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	RECIP.>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	SUPPORT VESSEL diesel	2065	99.7395	2393.75	10	52	1.46	0.83	50.03	1.50	10.92	0.38	0.22	13.01	0.39	2.84	
	TURBINE nat gas	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	RECIP.2 cycle lean nat gas	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	RECIP.4 cycle lean nat gas	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	RECIP.4 cycle rich nat gas	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	BURNER nat gas	0	0.00	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	MISC.	BPD	SCF/HR	COUNT													
	TANK-	0			0	0				0.00	0.00				0.00	0.00	
	FLARE-		0		0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	PROCESS VENT-		0		0	0				0.00	0.00				0.00	0.00	
	FUGITIVES-			500.0		365				0.25					1.10		
GLYCOL STILL VENT-		0		0	0				0.00					0.00			
DRILLING WELL TEST	OIL BURN	0			0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	GAS FLARE		208333.33		24	6		0.12	14.87	12.56	80.94		0.01	1.07	0.90	5.83	
<b>2020 YEAR TOTAL</b>							<b>23.43</b>	<b>13.56</b>	<b>820.13</b>	<b>36.97</b>	<b>256.63</b>	<b>4.90</b>	<b>2.82</b>	<b>169.58</b>	<b>7.05</b>	<b>42.59</b>	
EXEMPTION CALCULATION	DISTANCE FROM LAND IN MILES												289.71	289.71	289.71	289.71	14382.19
	8.7																

AIR EMISSIONS CALCULATIONS - THIRD YEAR

COMPANY	AREA	BLOCK	LEASE	PLATFORM	WELL		CONTACT	PHONE	REMARKS								
Cantium, LLC	Breton Sound	55	OCS-G 01372	FA, FAB	FA010, FA013, FAB1, FAB2, FAB3, FAB4		Dena Rodriguez	281-578-3388	Drill, complete, test and place three wells on production, drill and complete a dumpflood well; utili								
OPERATIONS	EQUIPMENT	RATING	MAX. FUEL	ACT. FUEL	RUN TIME		MAXIMUM POUNDS PER HOUR					ESTIMATED TONS					
					HP	GAL/HR	GAL/D										
	Diesel Engines		HP	SCF/HR	SCF/D												
	Nat. Gas Engines		HP	SCF/HR	SCF/D												
	Burners	MMBTU/HR	SCF/HR	SCF/D	HR/D	D/YR	PM	SOx	NOx	VOC	CO	PM	SOx	NOx	VOC	CO	
DRILLING	PRIME MOVER>600hp diesel	6905	333.5115	1964.00	24	150	4.87	2.79	167.30	5.02	36.50	2.15	1.23	73.89	2.22	16.12	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	PRIME MOVER>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	BURNER diesel	0			0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	AUXILIARY EQUIP<600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(crew)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	2065	99.7395	2393.75	10	150	1.46	0.83	50.03	1.50	10.92	1.09	0.63	37.52	1.13	8.19	
	VESSELS>600hp diesel(tugs)	8400	405.72	9737.28	24	2	5.92	3.40	203.52	6.11	44.41	0.14	0.08	4.88	0.15	1.07	
PIPELINE INSTALLATION	PIPELINE LAY BARGE diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	SUPPORT VESSEL diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	PIPELINE BURY BARGE diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	SUPPORT VESSEL diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(crew)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
FACILITY INSTALLATION	DERRICK BARGE diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	MATERIAL TUG diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(crew)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	VESSELS>600hp diesel(supply)	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
PRODUCTION	RECIP.<600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	RECIP.>600hp diesel	0	0	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	SUPPORT VESSEL diesel	2065	99.7395	2393.75	10	62	1.46	0.83	50.03	1.50	10.92	0.45	0.26	15.51	0.47	3.38	
	TURBINE nat gas	0	0	0.00	0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	RECIP.2 cycle lean nat gas	0	0	0.00	0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	RECIP.4 cycle lean nat gas	0	0	0.00	0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	RECIP.4 cycle rich nat gas	0	0	0.00	0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	BURNER nat gas	0	0.00	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	MISC.	BPD	SCF/HR	COUNT													
	TANK-	0			0	0				0.00					0.00		
	FLARE-		0		0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
	PROCESS VENT-		0		0	0				0.00				0.00	0.00	0.00	
	FUGITIVES-			500.0		365				0.25				1.10			
	GLYCOL STILL VENT-		0		0	0				0.00				0.00			
DRILLING WELL TEST	OIL BURN	0			0	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	GAS FLARE		0		0	0		0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	
<b>2021-2030 YEAR TOTAL</b>							<b>13.70</b>	<b>7.86</b>	<b>470.89</b>	<b>14.38</b>	<b>102.74</b>	<b>3.83</b>	<b>2.20</b>	<b>131.81</b>	<b>5.05</b>	<b>28.76</b>	
<b>EXEMPTION CALCULATION</b>	<b>DISTANCE FROM LAND IN MILES</b>											<b>289.71</b>	<b>289.71</b>	<b>289.71</b>	<b>289.71</b>	<b>14382.19</b>	
	8.7																

\* This AQR includes contingency drilling days each year for maintenance, workovers, recompletions, interventions and abandonment activities. Facility is within 100 km of Breton Sound, however contingency activity emissions will not occur for consecutive years.

### AIR EMISSIONS CALCULATIONS

COMPANY	AREA	BLOCK	LEASE	PLATFORM	WELL
Cantium, LLC	Breton Sound	55	OCS-G 01372	FA, FAB	FA010, FA013, FAB1,
Year	Emitted Substance				
	PM	SOx	NOx	VOC	CO
2019	2.72	1.56	93.66	3.90	20.44
2020	4.90	2.82	169.58	7.05	42.59
2021-2030	3.83	2.20	131.81	5.05	28.76
Allowable	289.71	289.71	289.71	289.71	14382.19

<b>Rig</b>	<b>Item description</b>	<b>Report Date</b>	<b>Used (bbls)</b>	<b>Used (gallons)</b>
Enterprise 264	DIESEL FUEL	2/1/19	33	1386
Enterprise 264	DIESEL FUEL	2/2/19	41	1722
Enterprise 264	DIESEL FUEL	2/3/19	59	2478
Enterprise 264	DIESEL FUEL	2/4/19	70	2940
Enterprise 264	DIESEL FUEL	2/5/19	36	1512
Enterprise 264	DIESEL FUEL	2/6/19	25	1050
Enterprise 264	DIESEL FUEL	2/7/19	27	1134
Enterprise 264	DIESEL FUEL	2/8/19	33	1386
Enterprise 264	DIESEL FUEL	2/9/19	66	2772
Enterprise 264	DIESEL FUEL	2/10/19	62	2604
Enterprise 264	DIESEL FUEL	2/11/19	69	2898
Enterprise 264	DIESEL FUEL	2/12/19	72	3024
Enterprise 264	DIESEL FUEL	2/13/19	76	3192
Enterprise 264	DIESEL FUEL	2/14/19	78	3276
Enterprise 264	DIESEL FUEL	2/15/19	84	3528
Enterprise 264	DIESEL FUEL	2/16/19	75	3150
Enterprise 264	DIESEL FUEL	3/1/19	8	336
Enterprise 264	DIESEL FUEL	3/2/19	8	336
Enterprise 264	DIESEL FUEL	3/3/19	25	1050
Enterprise 264	DIESEL FUEL	3/4/19	33	1386
Enterprise 264	DIESEL FUEL	3/5/19	27	1134
Enterprise 264	DIESEL FUEL	3/6/19	34	1428
Enterprise 264	DIESEL FUEL	3/7/19	28	1176
Enterprise 264	DIESEL FUEL	3/8/19	22	924
Enterprise 264	DIESEL FUEL	3/9/19	28	1176
Enterprise 264	DIESEL FUEL	3/10/19	33	1386
Enterprise 264	DIESEL FUEL	3/11/19	34	1428
Enterprise 264	DIESEL FUEL	3/12/19	33	1386
Enterprise 264	DIESEL FUEL	3/13/19	30	1260
Enterprise 264	DIESEL FUEL	3/14/19	29	1218
Enterprise 264	DIESEL FUEL	3/15/19	33	1386
Enterprise 264	DIESEL FUEL	3/16/19	22	924
Enterprise 264	DIESEL FUEL	3/17/19	11	462
Enterprise 264	DIESEL FUEL	3/18/19	22	924
Enterprise 264	DIESEL FUEL	3/19/19	20	840
Enterprise 264	DIESEL FUEL	3/20/19	17	714
Enterprise 264	DIESEL FUEL	3/21/19	16	672
Enterprise 264	DIESEL FUEL	3/22/19	25	1050
Enterprise 264	DIESEL FUEL	3/23/19	17	714
Enterprise 264	DIESEL FUEL	3/24/19	22	924
Enterprise 264	DIESEL FUEL	3/25/19	25	1050
Enterprise 264	DIESEL FUEL	3/26/19	29	1218
Enterprise 264	DIESEL FUEL	3/27/19	33	1386
Enterprise 264	DIESEL FUEL	3/28/19	55	2310

<b>Rig</b>	<b>Item description</b>	<b>Report Date</b>	<b>Used (bbls)</b>	<b>Used (gallons)</b>
Enterprise 264	DIESEL FUEL	3/29/19	33	1386
Enterprise 264	DIESEL FUEL	3/30/19	37	1554
Enterprise 264	DIESEL FUEL	3/31/19	63	2646
Enterprise 264	DIESEL FUEL	TOTAL	1758	73836

## SECTION 9 OIL SPILL INFORMATION

### 9.1 OIL SPILL RESPONSE PLANNING

All the proposed activities and facilities in this DOCD will be covered by the Oil Spill Response Plan (OSRP) filed by Cantium, LLC (Company No. 03481) dated August 2017 and last approved on April 12, 2019 (OSRP Control No. O-1011).

### 9.2 SPILL RESPONSE SITES

Primary Response Equipment Location	Preplanned Staging Location
Houma, LA	Houma, LA
Venice, LA	Venice, LA
Harvey, LA	Harvey, LA

### 9.3 OSRO INFORMATION

Cantium's primary equipment provider is Clean Gulf Associates. Clean Gulf Associates Services, LLC will provide closest available personnel, as well as a supervisor to operate the equipment.

### 9.4 WORST-CASE DISCHARGE SCENARIO DETERMINATION

Category	Drilling		Production	
	Regional OSRP WCD	DOCD WCD	Regional OSRP WCD	DOCD WCD
Type of Activity	<10 Miles Drilling	<10 Miles Drilling	<10 Miles Production	<10 Miles Production
Facility location (Area/Block)	BM 2	BS 55	ST 24	BS 55
Facility designation	CG072	FAB1	CM003	FAB1
Distance to nearest shoreline (miles)	5.1	8.7	6.8	8.7
Storage tanks & flowlines (bbl)	0	0	0	0
Lease term pipelines (bbl)	0	0	0	85
Uncontrolled blowout (bbl)	42,509	21,802	9,400	2,898
<b>Total Volume (bbl)</b>	<b>42,509</b>	<b>21,802</b>	<b>9,400</b>	<b>2,983</b>
Type of oil(s) (crude, condensate, diesel)	Crude	Crude	Crude	Crude
API gravity	27°	33°	27°	33°

Cantium has determined that the worst-case scenario from the activities proposed in this DOCD does not supersede the worst-case scenario from our approved Regional OSRP.



Since Cantium, LLC has the capability to respond to the worst-case spill scenario included in our Regional OSRP approved on April 12, 2019, and since the worst-case scenario determined for our DOCD does not replace the worst-case scenario in our Regional OSRP, Cantium, LLC hereby certifies that Cantium, LLC has the capability to respond, to the maximum extent practicable, to a worst-case discharge, or a substantial threat of such a discharge, resulting from the activities proposed in this DOCD.

#### **9.5 OIL SPILL RESPONSE DISCUSSION**

The Oil Spill Response Discussion is included as **Attachment 9-A**.

#### **9.6 MODELING REPORT**

Modeling reports are not required for the activities proposed in this plan.

# ATTACHMENT 9-A

## SPILL RESPONSE DISCUSSION

For the purpose of NEPA and Coastal Zone Management Act analysis, the largest spill volume originating from the proposed activity would be a well blowout during drilling operations, estimated to be 21,802 barrels of crude oil per day with an API gravity of 33°.

### Land Segment and Resource Identification

Trajectories of a spill and the probability of it impacting a land segment have been projected utilizing information in the BOEM Oil Spill Risk Analysis Model (OSRAM) for the Central and Western Gulf of Mexico available on the BOEM website. The results are shown in **Figure 1**. The BOEM OSRAM identifies the highest probability of impact to the shorelines of Plaquemines Parish, Louisiana days. Plaquemines Parish includes Barataria Bay, the Mississippi River Delta, Breton Sound and the affiliated islands and bays. This region is an extremely sensitive habitat and serves as a migratory, breeding, feeding and nursery habitat for numerous species of wildlife. Beaches in this area vary in grain particle size and can be classified as fine sand, shell or perched shell beaches. Sandy and muddy tidal flats are also abundant.

### Response

Cantium will make every effort to respond to the Worst Case Discharge as effectively as practicable. A description of the response equipment under contract to contain and recover the Worst Case Discharge is shown in **Figure 2**.

Using the estimated chemical and physical characteristics of crude oil, an ADIOS weathering model was run on a similar product from the ADIOS oil database. The results indicate 34% or approximately 7,413 barrels of crude oil would be evaporated/dispersed within 24 hours, with approximately 14,389 barrels remaining.

Natural Weathering Data: BS 55, Well FAB1	Barrels of Oil
WCD Volume (24 hrs)	21,802
Less 34% natural evaporation/dispersion	7,413
Remaining volume	14,389

**Figure 2** outlines equipment, personnel, materials and support vessels as well as temporary storage equipment available to respond to the worst case discharge. The volume accounts for the amount remaining after evaporation/dispersion at 24 hours. The list estimates individual times needed for procurement, load out, travel time to the site and deployment. **Figure 2** also indicates how operations will be supported.

Cantium's Oil Spill Response Plan includes alternative response technologies such as dispersants and in-situ burn. Strategies will be decided by Unified Command based on an operations safety analysis, the size of the spill, weather and potential impacts. If aerial dispersants are utilized, 8 sorties (9,600 gallons) from two of the DC-3 aircrafts and 4 sorties (8,000 gallons) from the

Basler aircraft would provide a daily dispersant capability of 7,540 barrels. If the conditions are favorable for in-situ burning, the proper approvals have been obtained and the proper planning is in place, in-situ burning of oil may be attempted. Slick containment boom would be immediately called out and on-scene as soon as possible. Offshore response strategies may include attempting to skim utilizing CGA spill response equipment, with a total derated skimming capacity of 144,940 barrels. Temporary storage associated with skimming equipment equals 4,747 barrels. If additional storage is needed, various storage barges with a total capacity 141,000 bbls may be mobilized and centrally located to provide temporary storage and minimize off-loading time. **Safety is first priority. Air monitoring will be accomplished and operations deemed safe prior to any containment/skimming attempts.**

If the spill went unabated, shoreline impact in Plaquemines Parish, Louisiana would depend upon existing environmental conditions. Shoreline protection would include the use of CGA's near shore and shallow water skimmers with a totaled derated skimming capacity of 57,759 barrels. Temporary storage associated with skimming equipment equals 1,152 barrels. If additional storage is needed, various storage barges with a total capacity 60,000 bbls may be mobilized and centrally located to provide temporary storage and minimize off-loading time. Onshore response may include the deployment of shoreline boom on beach areas, or protection and sorbent boom on vegetated areas. Letters of Intent from AMPOL and OMI Environmental will ensure access to 164,600 feet of 18" shoreline protection boom. **Figure 2** outlines individual times needed for procurement, load out, travel time to the site and deployment. Strategies would be based upon surveillance and real time trajectories that depict areas of potential impact given actual sea and weather conditions. Applicable Area Contingency Plans (ACPs), Geographic Response Plans (GRPs), and Unified Command (UC) will be consulted to ensure that environmental and special economic resources are correctly identified and prioritized to ensure optimal protection. Shoreline protection strategies depict the protection response modes applicable for oil spill clean-up operations. As a secondary resource, the State of Louisiana Initial Oil Spill Response Plan will be consulted as appropriate to provide detailed shoreline protection strategies and describe necessary action to keep the oil spill from entering Louisiana's coastal wetlands. The UC should take into consideration all appropriate items detailed in Tactics discussion of this Appendix. The UC and their personnel have the option to modify the deployment and operation of equipment to allow for a more effective response to site-specific circumstances. Cantium's contract Incident Management Team has access to the applicable ACP(s) and GRP(s).

Based on the anticipated worst case discharge scenario, Cantium can be onsite with contracted oil spill recovery equipment with adequate response capacity to contain and recover surface hydrocarbons, and prevent land impact, to the maximum extent practicable, within an estimated 48 hours (based on the equipment's Effective Daily Recovery Capacity (EDRC)).

### **Initial Response Considerations**

Actual actions taken during an oil spill response will be based on many factors to include but not be limited to:

- Safety
- Weather
- Equipment and materials availability
- Ocean currents and tides
- Location of the spill
- Product spilled
- Amount spilled
- Environmental risk assessments
- Trajectory and product analysis
- Well status, i.e., shut in or continual release

Cantium will take action to provide a safe, aggressive response to contain and recover as much of the spilled oil as quickly as it is safe to do so. In an effort to protect the environment, response actions will be designed to provide an “in-depth” protection strategy meant to recover as much oil as possible as far from environmentally sensitive areas as possible. Safety will take precedence over all other considerations during these operations.

Coordination of response assets will be supervised by the designation of a SIMOPS group as necessary for close quarter vessel response activities. Most often, this group will be used during source control events that require a significant number of large vessels operating independently to complete a common objective, in close coordination and support of each other. This group must also monitor the subsurface activities of each vessel (ROV, dispersant application, well control support, etc.). The SIMOPS group leader reports to the Source Control Section Chief.

In addition, these activities will be monitored by the Incident Management Team (IMT) and Unified Command via a structured Common Operating Picture (COP) established to track resource and slick movement in real time.

Upon notification of a spill, the following actions will be taken:

- Information will be confirmed
- An assessment will be made and initial objectives set
- OSROs and appropriate agencies will be notified
- ICS 201, Initial Report Form completed
- Initial Safety plan will be written and published
- Unified Command will be established
  - Overall safety plan developed to reflect the operational situation and coordinated objectives
  - Areas of responsibility established for Source Control and each surface operational site
  - On-site command and control established

## Offshore Response Actions

### Equipment Deployment

#### *Surveillance*

- Surveillance Aircraft: within two hours of QI notification, or at first light
- Provide trained observer to provide on site status reports
- Provide command and control platform at the site if needed
- Continual surveillance of oil movement by remote sensing systems, aerial photography and visual confirmation
- Continual monitoring of vessel assets using vessel monitoring systems

#### *Dispersant application assets*

- Put ASI on standby
- With the FOSC, conduct analysis to determine appropriateness of dispersant application (refer to Section 18)
- Gain FOSC approval for use of dispersants on the surface
- Deploy aircraft in accordance with a plan developed for the actual situation
- Coordinate movement of dispersants, aircraft, and support equipment and personnel
- Confirm dispersant availability for current and long range operations
- Start ordering dispersant stocks required for expected operations

#### *Containment boom*

- Call out early and expedite deployment to be on scene ASAP
- Ensure boom handling and mooring equipment is deployed with boom
- Provide continuing reports to vessels to expedite their arrival at sites that will provide for their most effective containment
- Use Vessels of Opportunity (VOO) to deploy and maintain boom

#### *Oceangoing Boom Barge*

- Containment at the source
- Increased/enhanced skimmer encounter rate
- Protection booming

#### *In-situ Burn assets*

- Determine appropriateness of in-situ burn operation in coordination with the FOSC and affected SOSC
- Determine availability of fire boom and selected ignition systems
- Start ordering fire boom stocks required for expected operations
- Contact boom manufacturer to provide training & tech support for operations, if required
- Determine assets to perform on water operation
- Build operations into safety plan
- Conduct operations in accordance with an approved plan
- Initial test burn to ensure effectiveness

### *Dedicated off-shore skimming systems*

#### *General*

- Deployed to the highest concentration of oil
- Assets deployed at safe distance from aerial dispersant and in-situ burn operations

#### *CGA HOSS Barge*

- Use in areas with heaviest oil concentrations
- Consider for use in areas of known debris (seaweed, and other floating materials)

#### *CGA 95' Fast Response Vessels (FRVs)*

- Designed to be a first vessel on scene
- Capable of maintaining the initial Command and Control function for on water recovery operations
- 24 hour oil spill detection capability
- Highly mobile and efficient skimming capability
- Use as far off-shore as safely possible

#### *CGA FRUs*

- To the area of the thickest oil
- Use as far off-shore as allowed
- VOOs 140' – 180' in length
- VOOs with minimum of 18' x 38' or 23' x 50' of optimum deck space
- VOOs in shallow water should have a draft of <10 feet when fully loaded

#### *T&T Koseq Skimming Systems*

- To the area of the thickest oil
- Use as far off-shore as allowed
- VOOs with a minimum of 2,000 bbls storage capacity
- VOOs at least 200' in length
- VOOs with deck space of 100' x 40' to provide space for arms, tanks, and crane
- VOOs for shallow water should be deck barges with a draft of <10 feet when fully loaded

#### *Storage Vessels*

- Establish availability of CGA contracted assets (See Appendix E)
- Early call out (to allow for tug boat acquisition and deployment speeds)
- Phase mobilization to allow storage vessels to arrive at the same time as skimming systems
- Position as closely as possible to skimming assets to minimize offloading time

### *Vessels of Opportunity (VOO)*

- Use Cantium's contracted resources as applicable
- Industry vessels are ideal for deployment of Vessel of Opportunity Skimming Systems (VOSS)
- Acquire additional resources as needed
- Consider use of local assets, i.e. fishing and pleasure craft for ISB operations or boom tending
- Expect mission specific and safety training to be required
- Plan with the US Coast Guard for vessel inspections
- Place VOOs in Division or Groups as needed
- Use organic on-board storage if appropriate
- Maximize non-organic storage appropriate to vessel limitations
- Decant as appropriate after approval to do so has been granted
- Assign bulk storage barges to each Division/Group
- Position bulk storage barges as close to skimming units as possible
- Utilize large skimming vessel (e.g. barges) storage for smaller vessel offloading
- Maximize skimming area (swath) to the optimum width given sea conditions and available equipment
- Maximize use of oleophilic skimmers in all operations, but especially offshore
- Nearshore, use shallow water barges and shuttle to skimming units to minimize offloading time
- Plan and equip to use all offloading capabilities of the storage vessel to minimize offloading time

### *Adverse Weather Operations:*

In adverse weather, when seas are  $\geq 3$  feet, the use of larger recovery and storage vessels, oleophilic skimmers, and large offshore boom will be maximized. KOSEQ Arm systems are built for rough conditions, and they should be used until their operational limit (9.8' seas) is met. Safety will be the overriding factor in all operations and will cease at the order of the Unified Command, vessel captain, or in an emergency, "stop work" may be directed by any crew member.

### **Surface Oil Recovery Considerations and Tactics (Offshore and Near-shore Operations)**

#### *Maximization of skimmer-oil encounter rate*

- Place barges in skimming task forces, groups, etc., to reduce recovered oil offloading time
- Place barges alongside skimming systems for immediate offloading of recovered oil when practicable
- Use two vessels, each with heavy sea boom, in an open-ended "V" configuration to funnel surface oil into a trailing skimming unit's organic, V-shaped boom and skimmer (see page 7, *CGA Equipment Guide Book and Tactic Manual (CGATM)*)

- Use secondary vessels and heavy sea boom to widen boom swath beyond normal skimming system limits (see page 15, CGATM)
- Consider night-time operations, first considering safety issues
- Utilize all available advanced technology systems ( IR, X-Band Radar, etc.) to determine the location of, and move to, recoverable oil
- Confirm the presence of recoverable oil prior to moving to a new location

*Maximize skimmer system efficiency*

- Place weir skimming systems in areas of calm seas and thick oil
- Maximize the use of oleophilic skimming systems in heavier seas
- Place less mobile, high EDRC skimming systems (e.g. HOSS Barge) in the largest pockets of the heaviest oil
- Maximize onboard recovered oil storage for vessels.
- Obtain authorization for decanting of recovered water as soon as possible
- Use smaller, more agile skimming systems to recover streamers of oil normally found farther from the source. Place recovered oil barges nearby

*Recovered Oil Storage*

- Smaller barges in larger quantities will increase flexibility for multi-location skimming operations
- Place barges in skimming task forces, groups, etc., to reduce recovered oil offloading time
- Procure and deploy the maximum number of portable tanks to support Vessel of Opportunity Skimming Systems if onboard storage is not available
- Maximize use of the organic recovered oil storage capacity of the skimming vessel

*Command, Control, and Communications (C<sup>3</sup>)*

- Publish, implement, and fully test an appropriate communications plan
- Design an operational scheme, maintaining a manageable span of control
- Designate and mark C<sup>3</sup> vessels for easy aerial identification
- Designate and employ C<sup>3</sup> aircraft for task forces, groups, etc.
- Use reconnaissance air craft and Rapid Response Teams (RAT) to confirm the presence of recoverable oil



### **On Water Recovery Group**

When the first skimming vessel arrives on scene, a complete site assessment will be conducted before recovery operations begin. Once it is confirmed that the air monitoring readings for O<sub>2</sub>, LEL, H<sub>2</sub>S, CO, VOC, and Benzene are all within the permissible limits, oil recovery operations may begin.

As skimming vessels arrive, they will be organized to work in areas that allow for the most efficient vessel operation and free vessel movement in the recovery of oil. Vessel groups will vary in structure as determined by the Operations Section of the Unified Command, but will generally consist, at a minimum, of the following dedicated assets:

- 3 to 5 – Offshore skimming vessels (recovery)
- 1 – Tank barge (temporary storage)
- 1 – Air asset (tactical direction)
- 2 – Support vessels (crew/utility for supply)
- 6 to 10 – Boom vessels (enhanced booming )

*Example (Note: Actual organization of TFs will be dependent on several factors including, asset availability, weather, spilled oil migration, currents, etc.)*

The 95' FRV Breton Island out of Venice arrives on scene and conducts an initial site assessment. Air monitoring levels are acceptable and no other visual threats have been observed. The area is cleared for safe skimming operations. The Breton Island assumes command and control (CoC) of on-water recovery operations until a dedicated non-skimming vessel arrives to relieve it of those duties.

A second 95' FRV arrives and begins recovery operations alongside the Breton Island. Several more vessels begin to arrive, including a third 95' FRV out of Galveston, the HOSS Barge (High Volume Open Sea Skimming System) out of Harvey, a boom barge (CGA 300) with 25,000' of 42" auto boom out of Leeville, and 9 Fast Response Units (FRUs) from the load-out location at C-Port in Port Fourchon.

As these vessels set up and begin skimming, they are grouped into task forces (TFs) as directed by the Operations Section of the Unified Command located at the command post.

Initial set-up and potential actions:

- A 1,000 meter safety zone has been established around the incident location for vessels involved in Source Control
- The HOSS Barge is positioned facing the incident location just outside of this safety zone or at the point where the freshest oil is reaching the surface
- The HOSS Barge engages its Oil Spill Detection (OSD) system to locate the heaviest oil and maintains that ability for 24-hour operations

- The HOSS Barge deploys 1,320' of 67" Sea Sentry boom on each side, creating a swath width of 800'
- The Breton Island and H.I. Rich skim nearby, utilizing the same OSD systems as the HOSS Barge to locate and recover oil
- Two FRUs join this group and it becomes TF1
- The remaining 7 FRUs are split into a 2 and 3 vessel task force numbered TF2 and TF3
- A 95' FRV is placed in each TF
- The boom barge (CGA 300) is positioned nearby and begins deploying auto boom in sections between two utility vessels (1,000' to 3,000' of boom, depending on conditions) with chain-link gates in the middle to funnel oil to the skimmers
- The initial boom support vessels position in front of TF2 and TF3
- A 100,000+ barrel offshore tank barge is placed with each task force as necessary to facilitate the immediate offload of skimming vessels

The initial task forces (36 hours in) may be structured as follows:

#### **TF 1**

- 1 – 95' FRV
- 1 – HOSS Barge with 3 tugs
- 2 – FRUs
- 1 – 100,000+ barrel tank barge and associated tug(s)
- 1 – Dedicated air asset for tactical direction
- 8 – 500' sections of auto boom with gates
- 8 – Boom-towing vessels
- 2 – Support vessels (crew/utility)

#### **TF 2**

- 1 – 95' FRV
- 4 – FRUs
- 1 – 100,000+ barrel tank barge and associated tug(s)
- 1 – Dedicated air asset for tactical direction
- 10 – 500' sections of auto boom with gates
- 10 – Boom-towing vessels
- 2 – Support vessels (crew/utility)

#### **TF 3**

- 1 – 95' FRV
- 3 – FRUs
- 1 – 100,000+ barrel tank barge and associated tug(s)
- 1 – Dedicated air asset for tactical direction
- 8 – 500' sections of auto boom with gates
- 8 – Boom-towing vessels
- 2 – Support vessels (crew/utility)

Offshore skimming equipment continues to arrive in accordance with the ETA data listed in figure H.3a; this equipment includes 2 AquaGuard skimmers and 11 sets of Koseq Rigid Skimming Arms. These high volume heavy weather capable systems will be divided into functional groups and assigned to specific areas by the Operations Section of the Unified Command.

At this point of the response, the additional TFs may assume the following configurations:

**TF 4**

- 2 – Sets of Koseq Rigid Skimming Arms w/ associated 200'+ PIDVs
- 1 – AquaGuard Skimmer
- 1 – 100,000+ barrel tank barge and associated tug(s)
- 1 – Dedicated air asset for tactical direction
- 2 – Support vessels (crew/utility)
- 6 – 500' sections of auto boom with gates
- 6 – Boom-towing vessels

**TF 5**

- 3 – Sets of Koseq Rigid Skimming Arms w/ associated 200'+ PIDVs
- 1 – AquaGuard Skimmer
- 1 – 100,000+ barrel tank barge and associated tug(s)
- 1 – Dedicated air asset for tactical direction
- 2 – Support vessels (crew/utility)
- 8 – 500' sections of auto boom with gates
- 8 – Boom-towing vessels

**TF 6**

- 3 – Sets of Koseq Rigid Skimming Arms w/ associated 200'+ PIDVs
- 1 – 100,000+ barrel tank barge and associated tug(s)
- 1 – Dedicated air asset for tactical direction
- 2 – Support vessels (crew/utility)
- 6 – 500' sections of auto boom with gates
- 6 – Boom-towing vessels

**TF 7**

- 3 – Sets of Koseq Rigid Skimming Arms w/ associated 200'+ PIDVs
- 1 – 100,000+ barrel tank barge and associated tug(s)
- 1 – Dedicated air asset for tactical direction
- 2 – Support vessels (crew/utility)
- 6 – 500' sections of auto boom with gates
- 6 – Boom-towing vessels

**CGA Minimum Acceptable Capabilities for Vessels of Opportunity (VOO)**

Minimum acceptable capabilities of Petroleum Industry Designed Vessels (PIDV) for conducting Vessel of Opportunity (VOO) skimming operations are shown in the table below. PIDVs are “purpose-built” to provide normal support to offshore oil and gas operators. They include but are not limited to utility boats, offshore supply vessels, etc. They become VOOs when tasked with oil spill response duties.

Capability	FRU	KOSEQ	AquaGuard
Type of Vessel	Utility Boat	Offshore Supply Vessel	Utility Boat
<b>Operating parameters</b>			
Sea State	3-5 ft max	9.8 ft max	3-5 ft max
Skimming speed	≤1 kt	≤3 kts	≤1 kt
<b>Vessel size</b>			
Minimum Length	100 ft	200 ft	100 ft
Deck space for: <ul style="list-style-type: none"> <li>• Tank(s)</li> <li>• Crane(s)</li> <li>• Boom Reels</li> <li>• Hydraulic Power Units</li> <li>• Equipment Boxes</li> </ul>	18x32 ft	100x40 ft	18x32 ft
<b>Communication Assets</b>	Marine Band Radio	Marine Band Radio	Marine Band Radio

**Tactical use of Vessels of Opportunity (VOO):** Cantium will take all possible measures to maximize the oil-to-skimmer encounter rate of all skimming systems, to include VOOs, as discussed in this section. VOOs will normally be placed within an On-water recovery unit as shown in figures below.

**Skimming Operations:** PIDVs are the preferred VOO skimming platform. OSROs are more versed in operating on these platforms and the vessels are generally large enough with crews more likely versed in spill response operations. They also have a greater possibility of having on-board storage capacity and the most likely vessels to be under contract, and therefore more readily available to the operator. These vessels would normally be assigned to an on-water recovery group/division (see figure below) and outfitted with a VOSS suited for their size and capabilities. Specific tactics used for skimming operations would be dependent upon many parameters which include, but are not limited to, safety concerns, weather, type VOSS on board, product being recovered, and area of oil coverage. Planners would deploy these assets with the objective of safely maximizing oil- to-skimmer encounter rate by taking actions to minimize non-skimming time and maximizing boom swath. Specific tactical configurations are shown in figures below.

**The Fast Response Unit (FRU):** A self-contained, skid based, skimming system that is deployed from the right side of a vessel of opportunity (VOO). An outrigger holds a 75' long section of air inflatable boom in place that directs oil to an apex for recovery via a Foilex 250 weir skimmer. The outrigger creates roughly a 40' swath width dependent on the VOO beam. The lip of the collection bowl on the skimmer is placed as close to the oil and water interface as possible to maximize oil recovery and minimize water retention. The skimmer then pumps all fluids recovered to the storage tank where it is allowed to settle, and with the approval of the Coast Guard, the water is decanted from the bottom of the tank back into the water ahead of the containment boom to be recycled through the system. Once the tank is full of as much pure recovered oil as possible it is offloaded to a storage barge for disposal in accordance with an approved disposal plan. A second 100 barrel storage tank can be added if the appropriate amount of deck space is available to use as secondary storage.

### **Tactical Overview**

*Mechanical Recovery* – The FRU is designed to provide fast response skimming capability in the offshore and nearshore environment in a stationary or advancing mode. It provides a rated daily recovery capacity of 4,100 barrels. An additional boom reel with 440' of offshore boom can be deployed along with the FRU, and a second support vessel for boom towing, to extend the swath width when attached to the end of the fixed boom. The range and sustainability offshore is dependent on the VOO that the unit is placed on, but generally these can stay offshore for extended periods. The FRU works well independently or assigned with other on-water recovery assets in a task force. In either case, it is most effective when a designated aircraft is assigned to provide tactical direction to ensure the best placement in recoverable oil.

*Maximum Sea Conditions* – Under most circumstances the FRU can maintain standard oil spill recovery operations in 2' to 4' seas. Ultimately, the Coast Guard licensed Captain in charge of the VOO (with input from the CGAS Supervisor assigned) will be responsible to determine when the sea conditions have surpassed the vessel's safe operating capabilities.

### **Possible Task Force Configuration** (Multiple VOOs can be deployed in a task force)

- 1 – VOO (100' to 165' Utility or Supply Vessel)
- 1 – Boom reel w/support vessel for towing
- 1 – Tank barge (offshore) for temporary storage
- 1 – Utility/Crewboat (supply)
- 1 – Designated spotter aircraft



**The VOSS (yellow) is being deployed and connected to an out-rigged arm. This is suitable for collection in both large pockets of oil and for recovery of streaming oil. The oil-to-skimmer encounter rate is limited by the length of the arm. Skimming pace is  $\leq 1$  knot.**



**Through the use of an additional VOO, and using extended sea boom, the swath of the VOSS is increased therefore maximizing the oil-to-skimmer encounter rate. Skimming pace is  $\leq 1$  knot.**

**The Koseq Rigid Sweeping Arm:** A skimming system deployed on a vessel of opportunity. It requires a large Offshore or Platform Supply Vessel (OSV/PSV), greater than 200' with at least 100' x 50' of free deck space. On each side of the vessel, a 50' long rigid framed Arm is deployed that consists of pontoon chambers to provide buoyancy, a smooth nylon face, and a hydraulically adjustable mounted weir skimmer. The Arm floats independently of the vessel and is attached by a tow bridle and a lead line. The movement of the vessel forward draws the rubber end seal of the arm against the hull to create a collection point for free oil directed to the weir by the Arm face. The collection weir is adjusted to keep the lip as close to the oil water interface as possible to maximize oil recovery while attempting to minimize excess water collection. A transfer pump (combination of positive displacement, screw type and centrifuge suited for highly viscous oils) pump the recovered liquid to portable tanks and/or dedicated fixed storage tanks onboard the vessel. After being allowed to sit and separate, with approval from the Coast Guard, the water can be decanted (pumped off) in front of the collection arm to be reprocessed through the system. Once full with as much pure recovered oil as possible, the oil is transferred to a temporary storage barge where it can be disposed of in accordance with an approved disposal plan.

### **Tactical Overview**


*Mechanical Recovery* – Deployed on large vessels of opportunity (VOO) the Koseq Rigid Sweeping Arms are high volume surge capacity deployed to increase recovery capacity at the source of a large oil spill in the offshore and outer nearshore environment of the Gulf of Mexico. They are highly mobile and sustainable in rougher sea conditions than normal skimming vessels (9.8' seas). The large Offshore Supply Vessels (OSV) required to deploy the Arms are able to remain on scene for extended periods, even when sea conditions pick up. Temporary storage on deck in portable tanks usually provides between 1,000 and 3,000 bbls. In most cases, the OSV will be able to pump 20% of its deadweight into the liquid mud tanks in accordance with the vessels Certificate of Inspection (COI). All storage can be offloaded utilizing the vessels liquid transfer system.

*Maximum Sea Conditions* - Under most circumstances the larger OSVs are capable of remaining on scene well past the Skimming Arms maximum sea state of 9.8'. Ultimately it will be the decision of the VOO Captain, with input from the T&T Supervisor onboard, to determine when the sea conditions have exceeded the safe operating conditions of the vessel.


*Command and Control* – The large OSVs in many cases have state of the art communication and electronic systems, as well as the accommodations to support the function of directing all skimming operations offshore and reporting back to the command post.

**Possible Task Force Configuration** (Multiple Koseq VOOs can be deployed in a task force)

- 1 –  $\geq$  200' Offshore Supply Vessels (OSV) with set of Koseq Arms
- 2 to 4 portable storage tanks (500 bbl)
- 1 – Modular Crane Pedestal System set (MCPS) or 30 cherry picker (crane) for deployment
- 1 – Tank barge (offshore) for temporary storage
- 1 – Utility/Crewboat (supply)
- 1 – Designated spotter aircraft
- 4 – Personnel (4 T&T OSRO)



Scattered oil is “caught” by two VOO and collected at the apex of the towed sea boom. The oil moves through a “gate” at that apex, forming a larger stream of oil which moves into the boom of the skimming vessel. Operations are paced at  $>1$ . A recovered oil barge stationed nearby to minimize time taken to offload recovered oil.



This is a depiction of the same operation as above but using KOSEQ Arms. In this configuration, the collecting boom speed dictates the operational pace at  $\geq 1$  knot to minimize entrainment of the oil.



### **Clean Gulf Associates (CGA) Procedure for Accessing Member-Contracted and other Vessels of Opportunity (VOOs) for Spill Response**

- CGA has procedures in place for CGA member companies to acquire vessels of opportunity (VOOs) from an existing CGA member's contracted fleet or other sources for the deployment of CGA portable skimming equipment including Koseq Arms, Fast Response Units (FRUs) and any other portable skimming system(s) deemed appropriate for the response for a potential or actual oil spill, WCD oil spill or a Spill of National Significance (SONS).
- CGA uses Port Vision, a web-based vessel and terminal interface that empowers CGA to track vessels through Automatic Identification System (AIS) and terminal activities using a Geographic Information System (GIS). It provides live AIS/GIS views of waterways showing current vessel positions, terminals, created vessel fleets, and points-of-interest. Through this system, CGA has the ability to get instant snapshots of the location and status of all vessels contracted to CGA members, day or night, from any web-enabled PC.

## Near Shore Response Actions

### *Timing*

- Put near shore assets on standby and deployment in accordance with planning based on the actual situation, actual trajectories and oil budgets
- VOO identification and training in advance of spill nearing shoreline if possible
- Outfitting of VOOs for specific missions
- Deployment of assets based on actual movement of oil

### *Considerations*

- Water depth, vessel draft
- Shoreline gradient
- State of the oil
- Use of VOOs
- Distance of surf zone from shoreline

### *Surveillance*

- Provide trained observer to direct skimming operations
- Continual surveillance of oil movement by remote sensing systems, aerial photography and visual confirmation
- Continual monitoring of vessel assets

### *Dispersant Use*

- Generally will not be approved within 3 miles of shore or with less than 10 meters of water depth
- Approval would be at Regional Response Team level (Region 6)

### *Dedicated Near Shore skimming systems*

- FRVs
- Egmpol and Marco SWS
- Operate with aerial spotter directing systems to observed oil slicks

### *VOO*

- Use Cantium's contracted resources as applicable
- Industry vessel are usually best for deployment of Vessel of Opportunity Skimming Systems (VOSS)
- Acquire additional resources as needed
- Consider use of local assets, i.e. fishing and pleasure craft
- Expect mission specific and safety training to be required
- Plan with the US Coast Guard for vessel inspections
- Operate with aerial spotter directing systems to oil patches

## **Shoreline Protection Operations**

### *Response Planning Considerations*

- Review appropriate Area Contingency Plan(s)
- Locate and review appropriate Geographic Response and Site Specific Plans
- Refer to appropriate Environmentally Sensitive Area Maps
- Capability for continual analysis of trajectories run periodically during the response
- Environmental risk assessments (ERA) to determine priorities for area protection
- Time to acquire personnel and equipment and their availability
- Refer to the State of Louisiana Initial Oil Spill Response Plan, Deep Water Horizon, dated 2 May 2010, as a secondary reference
- Aerial surveillance of oil movement
- Pre-impact beach cleaning and debris removal
- Shoreline Cleanup Assessment Team (SCAT) operations and reporting procedures
- Boom type, size and length requirements and availability
- Possibility of need for In-situ burning in near shore areas
- Current wildlife situation, especially status of migratory birds and endangered species in the area
- Check for Archeological sites and arrange assistance for the appropriate state agency when planning operations that may impact these areas

### *Placement of boom*

- Position boom in accordance with the information gained from references listed above and based on the actual situation
- Determine areas of natural collection and develop booming strategies to move oil into those areas
- Assess timing of boom placement based on the most current trajectory analysis and the availability of each type of boom needed. Determine an overall booming priority and conduct booming operations accordingly. Consider:
  - Trajectories
  - Weather forecast
  - Oil Impact forecast
  - Verified spill movement
  - Boom, manpower and vessel (shallow draft) availability
  - Near shore boom and support material, (stakes, anchors, line)

### *Beach Preparation - Considerations and Actions*

- Use of a 10 mile go/no go line to determine timing of beach cleaning
- SCAT reports and recommendations
- Determination of archeological sites and gaining authority to enter
- Monitoring of tide tables and weather to determine extent of high tides
- Pre cleaning of beaches by moving waste above high tide lines to minimize waste
- Determination of logistical requirements and arranging of waste removal and disposal

- Staging of equipment and housing of response personnel as close to the job site as possible to maximize on-site work time
- Boom tending, repair, replacement and security (use of local assets may be advantageous)
- Constant awareness of weather and oil movement for resource re-deployment as necessary
- Earthen berms and shoreline protection boom may be considered to protect sensitive inland areas
- Requisitioning of earth moving equipment
- Plan for efficient and safe use of personnel, ensuring:
  - A continual supply of the proper Personal Protective Equipment
  - Heating or cooling areas when needed
  - Medical coverage
  - Command and control systems (i.e. communications)
  - Personnel accountability measures
- Remediation requirements, i.e., replacement of sands, rip rap, etc.
- Availability of surface washing agents and associated protocol requirements for their use (see National Contingency Plan Product Schedule for list of possible agents)
- Discussions with all stakeholders, i.e., land owners, refuge/park managers, and others as appropriate, covering the following:
  - Access to areas
  - Possible response measures and impact of property and ongoing operations
  - Determination of any specific safety concerns
  - Any special requirements or prohibitions
  - Area security requirements
  - Handling of waste
  - Remediation expectations
  - Vehicle traffic control
  - Domestic animal safety concerns
  - Wildlife or exotic game concerns/issues

*Inland and Coastal Marsh Protection and Response  
Considerations and Actions*

- All considered response methods will be weighed against the possible damage they may do to the marsh. Methods will be approved by the Unified Command only after discussions with local Stakeholder, as identified above.
  - In-situ burn may be considered when marshes have been impacted
- Passive clean up of marshes should be considered and appropriate stocks of sorbent boom and/or sweep obtained.
- Response personnel must be briefed on methods to traverse the marsh, i.e.,
  - use of appropriate vessel
  - use of temporary walkways or road ways
- Discuss and gain approval prior cutting or moving vessels through vegetation
- Discuss use of vessels that may disturb wildlife, i.e., airboats
- Safe movement of vessels through narrow cuts and blind curves

- Consider the possibility that no response in a marsh may be best
- In the deployment of any response asset, actions will be taken to ensure the safest, most efficient operations possible. This includes, but is not limited to:
  - Placement of recovered oil or waste storage as near to vessels or beach cleanup crews as possible.
  - Planning for stockage of high use items for expeditious replacement
  - Housing of personnel as close to the work site as possible to minimize travel time
  - Use of shallow water craft
  - Use of communication systems appropriate ensure command and control of assets
  - Use of appropriate boom in areas that I can offer effective protection
  - Planning of waste collection and removal to maximize cleanup efficiency
- Consideration or on-site remediation of contaminated soils to minimize replacement operations and impact on the area

**Decanting Strategy**

Recovered oil and water mixtures will typically separate into distinct phases when left in a quiescent state. When separation occurs, the relatively clean water phase can be siphoned or decanted back to the recovery point with minimal, if any, impact. Decanting therefore increases the effective on-site oil storage capacity and equipment operating time. FOSC/SOSC approval will be requested prior to decanting operations. This practice is routinely used for oil spill recovery.

**CGA Equipment Limitations**

The capability for any spill response equipment, whether a dedicated or portable system, to operate in differing weather conditions will be directly in relation to the capabilities of the vessel the system is placed on. Most importantly, however, the decision to operate will be based on the judgment of the Unified Command and/or the Captain of the vessel, who will ultimately have the final say in terminating operations. Skimming equipment listed below may have operational limits which exceed those safety thresholds. As was seen in the Deepwater Horizon (DWH) oil spill response, vessel skimming operations ceased when seas reached 5-6 feet and vessels were often recalled to port when those conditions were exceeded. Systems below are some of the most up-to-date systems available and were employed during the DWH spill.

Boom	3 foot seas, 20 knot winds
Dispersants	Winds more than 25 knots Visibility less than 3 nautical miles Ceiling less than 1,000 feet.
FRU	8 foot seas
HOSS Barge/OSRB	8 foot seas
Koseq Arms	8 foot seas
OSRV	4 foot seas

### **Environmental Conditions in the GOM**

Louisiana is situated between the easterly and westerly wind belts, and therefore, experiences westerly winds during the winter and easterly winds in the summer. Average wind speed is generally 14-15 mph along the coast. Wave heights average 4 and 5 feet. However, during hurricane season, Louisiana has recorded wave heights ranging from 40 to 50 feet high and winds reaching speeds of 100 mph. Because much of southern Louisiana lies below sea level, flooding is prominent.

Surface water temperature ranges between 70 and 80 ° F during the summer months. During the winter, the average temperature will range from 50 and 60 ° F.

The Atlantic and Gulf of Mexico hurricane season is officially from 1 June to 30 November. 97% of all tropical activity occurs within this window. The Atlantic basin shows a very peaked season from August through October, with 78% of the tropical storm days, 87% of the minor (Saffir-Simpson Scale categories 1 and 2) hurricane days, and 96% of the major (Saffir-Simpson categories 3, 4 and 5) hurricane days occurring then. Maximum activity is in early to mid September. Once in a few years there may be a hurricane occurring "out of season" - primarily in May or December. Globally, September is the most active month and May is the least active month.

**FIGURE 1  
TRAJECTORY BY LAND SEGMENT**

<p>Trajectory of a spill and the probability of it impacting a land segment have been projected utilizing Cantium’s WCD and information in the BOEM Oil Spill Risk Analysis Model (OSRAM) for the Central and Western Gulf of Mexico available on the BOEM website using 3, 10, and 30 day impact. The results are tabulated below.</p>				
Area/Block	OCS-G	Launch Area	Land Segment and/or Resource	Conditional Probability (%)
<p>Drill, complete, test, produce 3 wells from FAB structure; Install FAB structure adjacent to existing FA Caisson; install 6’ bulk oil pipeline 6000’ in length from BS55 FAB to BS55 F</p> <p><b>BS 55, Well FAB1</b></p> <p><i>8.7 miles from shore</i></p>	G01372	C53	<p><b>Plaquemines, LA</b> St. Bernard, LA</p>	<p><i>3 day</i> <b>11</b> 2</p>
			<p>Lafourche, LA <b>Plaquemines, LA</b> St. Bernard, LA Hancock &amp; Harrison, MS Jackson, MS Mobile, AL Baldwin, AL Escambia, FL</p>	<p><i>10 day</i> 1 <b>25</b> 9 1 2 2 2 1</p>
			<p>Terrebonne, LA Lafourche, LA <b>Plaquemines, LA</b> St. Bernard, LA Hancock &amp; Harrison, MS Jackson, MS Mobile, AL Baldwin, AL Escambia, FL Okaloosa, FL Walton, FL Bay, FL Gulf, FL</p>	<p><i>30 day</i> 1 1 <b>31</b> 12 2 4 3 3 3 1 1 1 1</p>



**WCD Scenario– BASED ON WELL BLOWOUT DURING DRILLING OPERATIONS (8.7 miles from shore)**  
 14,389 bbls of crude oil (24 hour volume considering natural weathering)  
 API Gravity 33°

**FIGURE 2 – Equipment Response Time to BS 55, Well FAB1**

*Dispersants/Surveillance*

Dispersant/Surveillance	Dispersant Capacity (gal)	Persons Req.	From	Hrs to Procure	Hrs to Loadout	Travel to site	Total Hrs
ASI							
Basler 67T	2000	2	Houma	2	2	0.5	4.5
DC 3	1200	2	Houma	2	2	0.7	4.7
DC 3	1200	2	Houma	2	2	0.7	4.7
Aero Commander	NA	2	Houma	2	2	0.5	4.5

*Offshore Response*

Offshore Equipment Pre-Determined Staging	EDRC	Storage Capacity	VOO	Persons Required	From	Hrs to Procure	Hrs to Loadout	Hrs to GOM	Travel to Spill Site	Hrs to Deploy	Total Hrs
CGA											
HOSS Barge	76285	4000	3 Tugs	12	Harvey	6	0	12	8	2	28
95' FRV	22885	249	NA	6	Leeville	2	0	2	5.5	1	10.5
95' FRV	22885	249	NA	6	Venice	2	0	3	3	1	9
95' FRV	22885	249	NA	6	Vermilion	2	0	3	9	1	15
Boom Barge (CGA-300) 42" Auto Boom (25000')	NA	NA	1 Tug 50 Crew	4 (Barge) 2 (Per Crew)	Leeville	8	0	4	16	2	30
Enterprise Marine Services LLC (Available through contract with CGA)											
CTCo 2603	NA	25000	1 Tug	6	Amelia	18	0	6	23	1	48
CTCo 2607	NA	23000	1 Tug	6	Amelia	18	0	6	23	1	48
CTCo 2608	NA	23000	1 Tug	6	Amelia	18	0	6	23	1	48
CTCo 2609	NA	23000	1 Tug	6	Amelia	18	0	6	23	1	48
CTCo 5001	NA	47000	1 Tug	6	Amelia	18	0	6	23	1	48

**Staging Area: Venice**

Offshore Equipment With Staging	EDRC	Storage Capacity	VOO	Persons Req.	From	Hrs to Procure	Hrs to Loadout	Travel to Staging	Travel to Site	Hrs to Deploy	Total Hrs
CGA											
Hydro-Fire Boom	NA	NA	8 Utility	40	Harvey	0	24	2	5	6	37

*Nearshore Response*

Nearshore Equipment Pre-determined Staging	EDRC	Storage Capacity	VOO	Persons Required	From	Hrs to Procure	Hrs to Loadout	Hrs to GOM	Travel to Spill Site	Hrs to Deploy	Total Hrs
CGA											
Mid-Ship SWS	22885	249	NA	4	Venice	2	0	N/A	48	1	51
46' FRV	15257	65	NA	4	Venice	2	0	2	2	1	7
Enterprise Marine Services LLC (Available through contract with CGA)											
CTCo 2604	NA	20000	1 Tug	6	Amelia	25	0	6	16	1	48
CTCo 2605	NA	20000	1 Tug	6	Amelia	25	0	6	16	1	48
CTCo 2606	NA	20000	1 Tug	6	Amelia	25	0	6	16	1	48

**Staging Area: Venice**

Nearshore Equipment With Staging	EDRC	Storage Capacity	VOO	Persons Req.	From	Hrs to Procure	Hrs to Load Out	Travel to Staging	Travel to Deployment	Hrs to Deploy	Total Hrs
CGA											
SWS Egmopol	1810	100	NA	3	Galveston	2	2	13	2	1	20
SWS Egmopol	1810	100	NA	3	Morgan City	2	2	4.5	2	1	11.5
SWS Marco	3588	20	NA	3	Lake Charles	2	2	8	2	1	15
SWS Marco	3588	34	NA	3	Leeville	2	2	4.5	2	1	11.5
SWS Marco	3588	34	NA	3	Venice	2	2	2	2	1	7
Foilex Skim Package (TDS 150)	1131	50	NA	3	Lake Charles	4	12	8	2	2	28
Foilex Skim Package (TDS 150)	1131	50	NA	3	Galveston	4	12	13	2	2	33
Foilex Skim Package (TDS 150)	1131	50	NA	3	Harvey	4	12	2	2	2	22
4 Drum Skimmer (Magnum 100)	680	100	1 Crew	3	Lake Charles	2	2	8	2	1	15
4 Drum Skimmer (Magnum 100)	680	100	1 Crew	3	Harvey	2	2	2	2	1	9
2 Drum Skimmer (TDS 118)	240	100	1 Crew	3	Lake Charles	2	2	8	2	1	15
2 Drum Skimmer (TDS 118)	240	100	1 Crew	3	Harvey	2	2	2	2	1	9

*Shoreline Protection*

**Staging Area: Venice**

Shoreline Protection Boom	VOO	Persons Req.	Storage/Warehouse Location	Hrs to Procure	Hrs to Loadout	Travel to Staging	Travel to Deployment Site	Hrs to Deploy	Total Hrs
AMPOL (available through Letter of Intent)									
34,050' 18" Boom	13 Crew	26	New Iberia, LA	2	2	6	2	12	24
12,850' 18" Boom	7 Crew	14	Chalmette, LA	2	2	2.5	2	6	14.5
900' 18" Boom	1 Crew	2	Morgan City, LA	2	2	4.5	2	2	12.5
30,000' 18" Boom	13 Crew	26	Harvey, LA	2	2	2	2	12	20
1,700' 18" Boom	2 Crew	4	Venice, LA	2	2	0	2	2	8
14,750' 18" Boom	7 Crew	14	Port Arthur, TX	2	2	10	2	6	22
OMI Environmental (available through Letter of Intent)									
12,500' 18" Boom	6 Crew	12	New Iberia, LA	1	1	6	2	3	13
6,400' 18" Boom	3 Crew	6	Houston, TX	1	1	12	2	3	19
3,500' 18" Boom	2 Crew	4	Port Arthur, TX	1	1	10	2	3	17
4,000' 18" Boom	2 Crew	4	Longview, TX	1	1	13	2	3	20
4,850' 18" Boom	2 Crew	4	Belle Chasse, LA	1	1	2	2	3	9
8,000' 18" Boom	3 Crew	6	Port Allen, LA	1	1	5	2	3	12
2,000' 18" Boom	1 Crew	2	Houma, LA	1	1	4	2	3	11
2,500' 18" Boom	1 Crew	2	Morgan City, LA	1	1	5	2	3	12
1,600' 18" Boom	1 Crew	2	Gonzalez, LA	1	1	4	2	3	11
1,900' 18" Boom	1 Crew	2	St. James, LA	1	1	4	2	3	11
2,000' 18" Boom	1 Crew	2	Galliano, LA	1	1	4	2	3	11
1,000' 18" Boom	1 Crew	2	St. Rose, LA	1	1	3	2	3	10
1,000' 18" Boom	1 Crew	2	Hackberry, LA	1	1	9	2	3	16
5,800' 18" Boom	3 Crew	6	Venice, LA	1	1	0	2	3	7
13,300' 18" Boom	6 Crew	12	Harvey, LA	1	1	2	2	3	9

Wildlife Response	EDRC	Storage Capacity	VOO	Persons Req.	From	Hrs to Procure	Hrs to Loadout	Travel to Staging	Travel to Deployment	Hrs to Deploy	Total Hrs
CGA											
Wildlife Support Trailer	NA	NA	NA	2	Harvey	2	2	2	1	2	9
Bird Scare Guns (24)	NA	NA	NA	2	Harvey	2	2	2	1	2	9
Bird Scare Guns (12)	NA	NA	NA	2	Galveston	2	2	13	1	2	20
Bird Scare Guns (12)	NA	NA	NA	2	Aransas Pass	2	2	18	1	2	25
Bird Scare Guns (48)	NA	NA	NA	2	Lake Charles	2	2	8	1	2	15
Bird Scare Guns (24)	NA	NA	NA	2	Leeville	2	2	4.4	1	2	11.4

Response Asset	Total
Offshore EDRC	144,940
Offshore Recovered Oil Capacity	145,747
Nearshore / Shallow Water EDRC	57,759
Nearshore / Shallow Water Recovered Oil Capacity	61,152

## **SECTION 10 ENVIRONMENTAL MONITORING INFORMATION**

### **10.1 MONITORING SYSTEMS**

There are no environmental monitoring systems currently in place or planned for the proposed activities.

### **10.2 INCIDENTAL TAKES**

There is no reason to believe that any of the endangered species or marine mammals as listed in the Endangered Species Act (ESA) will be “taken” as a result of the operations proposed under this plan.

It has been documented that the use of explosives and/or seismic devices can affect marine life. Operations proposed in this plan will not be utilizing either of these devices.

Cantium will adhere to the requirements as set forth in the following documents, as applicable, to avoid or minimize impacts to any of the species listed in the ESA as a result of the operations conducted herein:

- NTL No. 2015-BSEE-G03, “Marine Trash and Debris Awareness and Elimination”
- NTL No. 2016-BOEM-G01, “Vessel Strike Avoidance and Injured/Dead Protected Species Reporting”
- NTL No. 2016-BOEM-G02, “Implementation of Seismic Survey Mitigation Measures and Protected Species Observer Program”

### **10.3 FLOWER GARDEN BANKS NATIONAL MARINE SANCTUARY**

Breton Sound Block 55 is not located in the Flower Garden Banks National Marine Sanctuary; therefore, relevant information is not required in this DOCD.

## SECTION 11 LEASE STIPULATIONS INFORMATION

Development activities are subject to the following stipulations attached to Lease OCS-G 01372, Breton Sound Block 55.

### 11.1 MARINE PROTECTED SPECIES

In accordance with the Federal Endangered Species Act and the Marine Mammal Protection Act, Cantium will:

- (a) Collect and remove flotsam resulting from activities related to exploration, development, and production of this lease;
- (b) Post signs in prominent places on all vessels and platforms used as a result of activities related to exploration, development, and production of this lease detailing the reasons (legal and ecological) why release of debris must be eliminated;
- (c) Observe for marine mammals and sea turtles while on vessels, reduce vessel speed to 10 knots or less when assemblages of cetaceans are observed, and maintain a distance of 90 meters or greater from whales, and a distance of 45 meters or greater from small cetaceans and sea turtles;
- (d) Employ mitigation measures prescribed by BOEM/BSEE or the National Marine Fisheries Service (NMFS) for all seismic surveys, including the use of an “exclusion zone” based upon the appropriate water depth, ramp-up and shutdown procedures, visual monitoring, and reporting;
- (e) Identify important habitats, including designated critical habitat, used by listed species (e.g., sea turtle nesting beaches, piping plover critical habitat), in oil spill contingency planning and require the strategic placement of spill cleanup equipment to be used only by personnel trained in less-intrusive cleanup techniques on beaches and bay shores; and
- (f) Immediately report all sightings and locations of injured or dead protected species (e.g., marine mammals and sea turtles) to the appropriate stranding network. If oil and gas industry activity is responsible for the injured or dead animal (e.g., because of a vessel strike), the responsible parties should remain available to assist the stranding network. If the injury or death was caused by a collision with the lessee’s vessel, the lessee must notify BOEM within 24 hours of the strike.

BOEM and BSEE issue Notices to Lessees (NTLs), which more fully describe measures implemented in support of the above-mentioned implementing statutes and regulations, as well as measures identified by the U.S. Fish and Wildlife Service and NMFS arising from, among others, conservation recommendations, rulemakings pursuant to the MMPA, or consultation. The lessee and its operators, personnel, and subcontractors, while undertaking activities authorized under this lease, must implement and comply with the specific mitigation measures

outlined in NTL No. 2016-BOEM-G01, "Vessel Strike Avoidance and Injured/Dead Protected Species Reporting;" NTL No. 2016-BOEM-G02, "Implementation of Seismic Survey Mitigation Measures and Protected Species Observer Program;" and NTL No. 2015-BSEE-G03, "Marine Trash and Debris Awareness and Elimination." At the lessee's option, the lessee, its operators, personnel, and contractors may comply with the most current measures to protect species in place at the time an activity is undertaken under this lease, including but not limited to new or updated versions of the NTLs identified in this paragraph. The lessee and its operators, personnel, and subcontractors will be required to comply with the mitigation measures, identified in the above referenced NTLs, and additional measures in the conditions of approvals for their plans or permits.

## **SECTION 12**

### **ENVIRONMENTAL MITIGATION MEASURES INFORMATION**

#### **12.1 MEASURES TAKEN TO AVOID, MINIMIZE, AND MITIGATE IMPACTS**

This plan does not propose activities for which the state of Florida is an affected state; therefore, mitigation information is not required for the activities proposed in this plan.

#### **12.2 INCIDENTAL TAKES**

Cantium will adhere to the requirements set forth in the following documents, as applicable, to avoid or minimize impacts to any of the species listed in the Endangered Species Act (ESA) as a result of the operations conducted herein:

- NTL No. 2015-BSEE-G03, "Marine Trash and Debris Awareness and Elimination"
- NTL No. 2016-BOEM-G01, "Vessel Strike Avoidance and Injured/Dead Protected Species Reporting"
- NTL No. 2016-BOEM-G02, "Implementation of Seismic Survey Mitigation Measures and Protected Species Observer Program"



## **SECTION 13 RELATED FACILITIES AND OPERATIONS INFORMATION**

### **13.1 RELATED OCS FACILITIES AND OPERATIONS**

The BS 55 FAB platform will be set adjacent to the existing BS 55 Caisson FA. The FAB structure will be a dual level well protector platform supported by a 48" caisson with a 20" internal well conductor and three 20" exterior well conductors.

### **13.2 TRANSPORTATION SYSTEM**

A 4-inch pipeline (Segment No. 00068) was installed to transport produced hydrocarbons from Platform FA to Platform F in Breton Sound Block 55 for processing. A 6-inch bulk oil pipeline 6000 feet in length will be installed from BS 55 FAB to BS 55 Platform F to support the increased liquid production rate.

### **13.3 PRODUCED LIQUID HYDROCARBONS TRANSPORTATION VESSELS**

There will not be any transfers of liquid hydrocarbons other than via pipeline.

## SECTION 14 SUPPORT VESSELS AND AIRCRAFT INFORMATION

### 14.1 GENERAL

The most practical, direct route from the shorebase as permitted by weather and traffic conditions will be utilized. Information regarding the vessels and aircraft to be used to support the proposed activities is provided in the table below.

Type	Maximum Fuel Tank Capacity	Maximum Number in Area at Any Time (drlg / prod)	Trip Frequency or Duration (drlg / prod)
Tug boat	59,548 gal	2 / 0	2 total / 0
Supply boat	7,240 gal	1 / 1	7x week / 2x week
Pipeline Lay Barge	1,500 gal	1 / 0	1 total / 0
Pipeline Bury Barge	1,500 gal	1 / 0	1 total / 0
Lift Boat	17,000 gal	1 / 0	1 total / 0
Utility Boat	4,000 gal	1 / 0	1 total / 0
Helicopter	560 gal	As Required	As Required

### 14.2 DIESEL OIL SUPPLY VESSELS

Information regarding vessels to be used to supply diesel oil for fuel and other purposes is provided in the table below.

Size of Fuel Supply Vessel (ft)	Capacity of Fuel Supply Vessel	Frequency of Fuel Transfers	Route Fuel Supply Vessel Will Take
180	63,000 gal	weekly	Shortest route from Shorebase to block

### 14.3 DRILLING FLUID TRANSPORTATION

Drilling fluid transportation information is not required to be submitted with this plan.

### 14.4 SOLID AND LIQUID WASTE TRANSPORTATION

A table, "Wastes You Will Transport and/or Dispose of Onshore," is included as **Attachment 14-A**.

### 14.5 VICINITY MAP

A vicinity map showing the location of the activities proposed herein relative to the shoreline with the distance of the proposed activities from the shoreline and the primary routes of the support vessels and aircraft that will be used when traveling between the onshore support facilities and the drilling unit is included as **Attachment 14-B**.

# ATTACHMENT 14-A


## WASTE AND SURPLUS ESTIMATED TO BE TRANSPORTED AND/OR DISPOSED OF ONSHORE

please specify whether the amount reported is a total or per well

Projected generated waste		Solid and Liquid Wastes transportation	Waste Disposal		
Type of Waste	Composition	Transport Method	Name/Location of Facility	Amount	Disposal Method
<b>Will drilling occur ? If yes, fill in the muds and cuttings.</b>					
Water-based drilling fluid or mud	NA				
Synthetic-based drilling fluid or mud	Synthetic Fluid	Shipped to shore in below deck storage tanks	R360 Environmental, Venice	11,000 bbls/well	Recycled or Land fill
Oil-based drilling fluid or mud	NA				
Cuttings wetted with water-based fluid	NA				
Cuttings wetted with synthetic-based fluid	NA				
Cuttings wetted with oil-based fluids	NA				
<b>Will you produce hydrocarbons? If yes fill in for produced sand.</b>					
Produced sand	NA				
<b>Will you have additional wastes that are not permitted for discharge? If yes, fill in the appropriate rows.</b>					
Trash and debris	Plastic, paper, aluminum	barged in a storage bin	Total Waste Solutions, Venice	15,000 lbs/well	Recycled or Land fill
Used oil	Oil	barged in 55 gal drums	R360 Environmental, Venice	30 drums/well	Recycled
Wash water	Water	Below deck storage tanks on offshore support vessels	R360 Environmental, Venice	2,500 bbls/well	Disposal
Chemical product wastes	Misc.	barged in a storage bin	R360 Environmental, Venice	1,000 lbs/well	Disposal
NOTE: If you will not have a type of waste, enter NA in the row.					



# Cantium, LLC



## SECTION 15 ONSHORE SUPPORT FACILITIES INFORMATION

### 15.1 GENERAL

The onshore facilities to be used to provide supply and service support for the proposed activities are provided in the table below.

Name	Location	Existing/New/Modified
EPS	Venice, Louisiana	Existing
Bristow Helicopters	Golden Meadow, Louisiana	Existing

### 15.2 SUPPORT BASE CONSTRUCTION OR EXPANSION

There will be no new construction of an onshore support base, nor will Cantium expand the existing shorebase as a result of the operations proposed in this DOCD.

### 15.3 SUPPORT BASE CONSTRUCTION OR EXPANSION TIMETABLE

A support base construction or expansion timetable is not required for the activities proposed in this plan.

### 15.4 WASTE DISPOSAL

A table, "Wastes You Will Transport and/or Dispose of Onshore," is included as **Attachment 14-A**.

## SECTION 16 COASTAL ZONE MANAGEMENT (CZM) INFORMATION

Under direction of the Coastal Zone Management Act (CZMA), the states of Louisiana and Mississippi developed Coastal Zone Management Programs (CZMP) to allow for the supervision of significant land and water use activities that take place within or that could significantly affect the Louisiana and Mississippi coastal zones.

Measures will be taken to avoid or mitigate the probable impacts to the Louisiana and Mississippi shores. Cantium will operate in compliance with existing federal and state laws, regulations, and resultant enforceable program policies in Louisiana's and Mississippi's Coastal Zone Management Programs.

The OCS related oil and gas exploratory and development activities having potential impact on the Louisiana and Mississippi Coastal Zones are based on the location of the proposed facilities, access to those sites, best practical techniques for drilling locations, drilling equipment guidelines for the prevention of adverse environmental effects, effective environmental protection, emergency plans and contingency plans.

Relevant enforceable policies were considered in certifying consistency for Louisiana. A certificate of Coastal Zone Management Consistency for the state of Louisiana is included as **Attachment 16-A**.

The policies and corresponding sections within this Development Operations Coordination Document identified by the State of Mississippi Coastal Program (MCP) as being related to OCS Plans are provided in the table below.

### **Enforceable Program Policies of the Mississippi Coastal Program (MCP)**

**Goal 1:** To provide for reasonable industrial expansion in the coastal area and to ensure the efficient utilization of waterfront industrial sites so that suitable sites are conserved for water dependent industry.

Goal 1 is addressed in Section 15. The proposed activities provide no industrial expansion in the coastal area of Mississippi; therefore, Mississippi coastal areas will be conserved for water dependent industry.

**Goal 2:** To favor the preservation of the coastal wetlands and ecosystems, except where a specific alteration of specific coastal wetlands would serve a higher public interest in compliance with the public purposes of the public trust in which the coastal wetlands are held.

Goal 2 is addressed in Section 17. All proposed activities shall avoid to the maximum extent practicable significant impact to Mississippi's coastal wetlands and ecosystems.

**Goal 3: To protect, propagate and conserve the state’s seafood and aquatic life in connection with the revitalization of the seafood industry of the State of Mississippi.**

Goal 3 is addressed in Section 17. All proposed activities shall avoid to the maximum extent practicable significant impact to Mississippi’s seafood industry.

**Goal 4: To conserve the air and waters of the state, and to protect, maintain and improve the quality thereof for public use, for the propagation of wildlife, fish and aquatic life, and for domestic, agricultural, industrial, recreational and other legitimate beneficial uses.**

Goal 4 is addressed in Sections 2, 8 and 17. All proposed activities shall avoid to the maximum extent practicable significant impact to Mississippi’s seafood industry.

**Goal 5: To put to beneficial use to the fullest extent of which they are capable the water resources of the state, and to prevent the waste, unreasonable use, or unreasonable method of use of water.**

The proposed activities are supported by a shorebase located in Louisiana and shall avoid to the maximum extent practicable significant impact to Mississippi’s water resources.

**Goal 6: To preserve the state’s historical and archaeological resources, to prevent their destruction, and to enhance these resources wherever possible.**

Goal 6 is addressed in Sections 3 and 17. All proposed activities shall avoid to the maximum extent practicable significant impact to Mississippi’s historical and archaeological resources.

**Goal 7: To encourage the preservation of natural scenic qualities in the coastal area.**

Goal 7 is addressed in Sections 7, 8, 9 and 17. All proposed activities shall avoid to the maximum extent practicable significant impact to Mississippi’s natural scenic qualities in the coastal area.

**Goal 8: To assist local governments in the provision of public facilities services in a manner consistent with the coastal program.**

All proposed activities are supported by a shorebase in Louisiana and shall avoid to the maximum extent practicable significant impact to Mississippi’s local governments.

A certificate of Coastal Zone Management Consistency for the state of Mississippi is included as **Attachment 16-A.**

ATTACHMENT 16-A

**COASTAL ZONE MANAGEMENT  
CONSISTENCY CERTIFICATION  
DEVELOPMENT OPERATIONS COORDINATION DOCUMENT  
BRETON SOUND BLOCK 55 (SL) / MAIN PASS BLOCKS 42 / 43 (BHL)  
OCS-G 01372 (SL) / OCS 00375 / 01452 (BHL)**

The proposed activity complies with the enforceable policies of the Louisiana approved management program and will be conducted in a manner consistent with such program.

Cantium, LLC

Lessee or Operator

Margaret Anderson  
Certifying Official

01 July 2019  
Date



**COASTAL ZONE MANAGEMENT  
CONSISTENCY CERTIFICATION  
DEVELOPMENT OPERATIONS COORDINATION DOCUMENT  
BRETON SOUND BLOCK 55 (SL) / MAIN PASS BLOCKS 42 / 43 (BHL)  
OCS-G 01372 (SL) / OCS 00375 / 01452 (BHL)**

The proposed activity complies with the enforceable policies of the Mississippi approved management program and will be conducted in a manner consistent with such program.

Cantium, LLC

Lessee or Operator

Margaret Anderson  
Certifying Official

01 July 2019  
Date

**SECTION 17  
ENVIRONMENTAL IMPACT ANALYSIS (EIA)**

The Environmental Impact Analysis is included as **Attachment 17-A**.

# ATTACHMENT 17-A

## Cantium, LLC (Cantium)

### Supplemental Development Operations Coordination Document Breton Sound Block 55 OCS-G 01372

#### (A) IMPACT PRODUCING FACTORS

#### ENVIRONMENTAL IMPACT ANALYSIS WORKSHEET

Environment Resources	Impact Producing Factors (IPFs) Categories and Examples Refer to recent GOM OCS Lease Sale EIS for a more complete list of IPFs					
	Emissions (air, noise, light, etc.)	Effluents (muds, cutting, other discharges to the water column or seafloor)	Physical disturbances to the seafloor (rig or anchor emplacements, etc.)	Wastes sent to shore for treatment or disposal	Accidents (e.g., oil spills, chemical spills, H <sub>2</sub> S releases)	Discarded Trash & Debris
<b>Site-specific at Offshore Location</b>						
Designated topographic features		(1)	(1)		(1)	
Pinnacle Trend area live bottoms		(2)	(2)		(2)	
Eastern Gulf live bottoms		(3)	(3)		(3)	
Benthic communities			(4)			
Water quality		X	X		X	
Fisheries		X	X		X	
Marine Mammals	X(8)	X			X(8)	X
Sea Turtles	X(8)	X			X(8)	X
Air quality	X(9)					
Shipwreck sites (known or potential)			X(7)			
Prehistoric archaeological sites			X(7)			
<b>Vicinity of Offshore Location</b>						
Essential fish habitat		X	X		X(6)	
Marine and pelagic birds	X				X	X
Public health and safety					(5)	
<b>Coastal and Onshore</b>						
Beaches					X(6)	X
Wetlands					X(6)	
Shore birds and coastal nesting birds					X(6)	X
Coastal wildlife refuges					X	
Wilderness areas					X	

## Footnotes for Environmental Impact Analysis Matrix

- 1) Activities that may affect a marine sanctuary or topographic feature. Specifically, if the well or platform site or any anchors will be on the seafloor within the:
  - 4-mile zone of the Flower Garden Banks, or the 3-mile zone of Stetson Bank;
  - 1000-m, 1-mile or 3-mile zone of any topographic feature (submarine bank) protected by the Topographic Features Stipulation attached to an OCS lease;
  - Essential Fish Habitat (EFH) criteria of 500 ft. from any no-activity zone; or
  - Proximity of any submarine bank (500 ft. buffer zone) with relief greater than 2 meters that is not protected by the Topographic Features Stipulation attached to an OCS lease.
- 2) Activities with any bottom disturbance within an OCS lease block protected through the Live Bottom (Pinnacle Trend) Stipulation attached to an OCS lease.
- 3) Activities within any Eastern Gulf OCS block where seafloor habitats are protected by the Live Bottom (Low-Relief) Stipulation attached to an OCS lease.
- 4) Activities on blocks designated by the BOEM as being in water depths 300 meters or greater.
- 5) Exploration or production activities where H<sub>2</sub>S concentrations greater than 500 ppm might be encountered.
- 6) All activities that could result in an accidental spill of produced liquid hydrocarbons or diesel fuel that you determine would impact these environmental resources. If the proposed action is located a sufficient distance from a resource that no impact would occur, the EIA can note that in a sentence or two.
- 7) All activities that involve seafloor disturbances, including anchor emplacements, in any OCS block designated by the BOEM as having high-probability for the occurrence of shipwrecks or prehistoric sites, including such blocks that will be affected that are adjacent to the lease block in which your planned activity will occur. If the proposed activities are located a sufficient distance from a shipwreck or a prehistoric site that no impact would occur, the EIA can note that in a sentence or two.
- 8) All activities that you determine might have an adverse effect on endangered or threatened marine mammals or sea turtles or their critical habitats.
- 9) Production activities that involve transportation of produced fluids to shore using shuttle tankers or barges.

## **(B) ANALYSIS**

### **Site-Specific at Breton Sound Block 55**

Proposed operations consist of the drilling, completion, testing, and commencement of production from 3 wells from the FAB structure. The FAB structure is also proposed to be installed adjacent to the existing FA caisson as part of these proposed operations. All proposed wells will have surface locations in Breton Sound Block 55 with bottomhole locations as follows: Well #FAB1 will have a bottomhole location in Main Pass Block 42 while Wells #FAB2 and #FAB3 will have bottomhole locations in Main Pass Block 43. Additionally, a 6,000-foot long pipeline, measuring 6 inches in diameter, will be installed from the Breton Sound Block 55 FAB structure to the existing Breton Sound Block 55 F structure.

Operations will be conducted with a jack-up rig.

#### **1. Designated Topographic Features**

Potential IPFs on topographic features include physical disturbances to the seafloor, effluents, and accidents.

**Physical disturbances to the seafloor:** Breton Sound Block 55 is 62 miles from the closest designated Topographic Features Stipulation Block (Sackett Bank); therefore, no adverse impacts are expected.

**Effluents:** Breton Sound Block 55 is 62 miles from the closest designated Topographic Features Stipulation Block (Sackett Bank); therefore, no adverse impacts are expected.

**Accidents:** It is unlikely that an accidental surface or subsurface spill would occur from the proposed activities (refer to statistics in **Item 5**, Water Quality). Oil spills cause damage to benthic organisms only if the oil contacts the organisms. Oil from a surface spill can be driven into the water column; measurable amounts have been documented down to a 10 m depth. At this depth, the oil is found only at concentrations several orders of magnitude lower than the amount shown to have an effect on corals. Because the crests of topographic features in the Northern Gulf of Mexico are found below 10 m, no oil from a surface spill could reach their sessile biota. Oil from a subsurface spill is not applicable due to the distance of these blocks from a topographic area. The activities proposed in this plan will be covered by Cantium's Regional OSRP (refer to information submitted in **Section 9**).

There are no other IPFs (including emissions and wastes sent to shore for disposal) from the proposed activities, which could impact topographic features.

## **2. Pinnacle Trend Area Live Bottoms**

Potential IPFs on pinnacle trend area live bottoms include physical disturbances to the seafloor, effluents, and accidents.

**Physical disturbances to the seafloor:** Breton Sound Block 55 is 35 miles from the closest live bottom (pinnacle trend) area; therefore, no adverse impacts are expected.

**Effluents:** Breton Sound Block 55 is 35 miles from the closest live bottom (pinnacle trend) area; therefore, no adverse impacts are expected.

**Accidents:** It is unlikely that an accidental surface or subsurface spill would occur from the proposed activities (refer to statistics in **Item 5**, Water Quality). Oil spills have the potential to foul benthic communities and cause lethal and sublethal effects on live bottom organisms. Oil from a surface spill can be driven into the water column; measurable amounts have been documented down to a 10 m depth. At this depth, the oil is found only at concentrations several orders of magnitude lower than the amount shown to have an effect on marine organisms. Oil from a subsurface spill is not applicable due to the distance of these blocks from a live bottom (pinnacle trend) area. The activities proposed in this plan will be covered by Cantium's Regional OSRP (refer to information submitted in **Section 9**).

There are no other IPFs (including emissions and wastes sent to shore for disposal) from the proposed activities which could impact a live bottom (pinnacle trend) area.

## **3. Eastern Gulf Live Bottoms**

Potential IPFs on Eastern Gulf live bottoms include physical disturbances to the seafloor, effluents, and accidents.

**Physical disturbances to the seafloor:** Breton Sound Block 55 is not located in an area characterized by the existence of live bottoms, and this lease does not contain a Live-Bottom Stipulation requiring a photo documentation survey and survey report.

**Effluents:** Breton Sound Block 55 is not located in an area characterized by the existence of live bottoms; therefore, no adverse impacts are expected.

**Accidents:** It is unlikely that an accidental surface or subsurface spill would occur from the proposed activities (refer to statistics in **Item 5**, Water Quality). Oil spills cause damage to live bottom organisms only if the oil contacts the organisms. Oil from a surface spill can be driven into the water column; measurable amounts have been documented down to a 10 m depth. At this depth, the oil is found only at concentrations several orders of magnitude lower than the amount shown to have an effect on marine invertebrates. Oil from a subsurface spill is not

applicable due to the distance of these blocks from a live bottom area. The activities proposed in this plan will be covered by Cantium's Regional OSRP (refer to information submitted in **Section 9**).

There are no other IPFs (including emissions and wastes sent to shore for disposal) from the proposed activities which could impact an Eastern Gulf live bottom area.

#### **4. Benthic Communities**

There are no IPFs (including emissions, physical disturbances to the seafloor, wastes sent to shore for disposal, or accidents) from the proposed activities that could cause impacts to benthic communities.

Operations proposed in this plan are in water depths of 28 feet. High-density benthic communities are found only in water depths greater than 984 feet (300 meters); therefore, Cantium's proposed operations in Breton Sound Block 55 would not cause impacts to benthic communities.

#### **5. Water Quality**

IPFs that could result in water quality degradation from the proposed operations in Breton Sound Block 55 include disturbances to the seafloor, effluents and accidents.

**Physical disturbances to the seafloor:** Bottom area disturbances resulting from the emplacement of drill rigs, the drilling of wells and the installation of platforms and pipelines would increase water-column turbidity and re-suspension of any accumulated pollutants, such as trace metals and excess nutrients. This would cause short-lived impacts on water quality conditions in the immediate vicinity of the emplacement operations.

**Effluents:** Levels of contaminants in drilling muds and cuttings and produced water discharges, discharge-rate restrictions and monitoring and toxicity testing are regulated by the EPA NPDES permit, thereby eliminating many significant biological or ecological effects. Operational discharges are not expected to cause significant adverse impacts to water quality.

**Accidents:** Oil spills have the potential to alter offshore water quality; however, it is unlikely that an accidental surface or subsurface spill would occur from the proposed activities. Between 1980 and 2000, OCS operations produced 4.7 billion barrels of oil and spilled only 0.001 percent of this oil, or 1 bbl for every 81,000 bbl produced. The spill risk related to a diesel spill from drilling operations is even less. Between 1976 and 1985, (years for which data were collected), there were 80 reported diesel spills greater than one barrel associated with drilling activities. Considering that there were 11,944 wells drilled, this is a 0.7 percent probability of an occurrence. If a spill were to occur, the water quality of marine waters would be temporarily affected by the dissolved components and small oil droplets. Dispersion by currents and microbial degradation would remove the oil from the water column and dilute the constituents to

background levels. Historically, changes in offshore water quality from oil spills have only been detected during the life of the spill and up to several months afterwards. Most of the components of oil are insoluble in water and therefore float. The activities proposed in this plan will be covered by Cantium's Regional Oil Spill Response Plan (refer to information submitted in **Section 9**).

There are no other IPFs (including emissions, physical disturbances to the seafloor, and wastes sent to shore for disposal) from the proposed activities which could cause impacts to water quality.

## **6. Fisheries**

IPFs that could cause impacts to fisheries as a result of the proposed operations in Breton Sound Block 55 include physical disturbances to the seafloor, effluents and accidents.

**Physical disturbances to the seafloor:** The emplacement of a structure or drilling rig results in minimal loss of bottom trawling area to commercial fishermen. Pipelines cause gear conflicts which result in losses of trawls and shrimp catch, business downtime and vessel damage. Most financial losses from gear conflicts are covered by the Fishermen's Contingency Fund (FCF). The emplacement and removal of facilities are not expected to cause significant adverse impacts to fisheries.

**Effluents:** Effluents such as drilling fluids and cuttings discharges contain components and properties which are detrimental to fishery resources. Moderate petroleum and metal contamination of sediments and the water column can occur out to several hundred meters down-current from the discharge point. Offshore discharges are expected to disperse and dilute to very near background levels in the water column or on the seafloor within 3,000 m of the discharge point, and are expected to have negligible effect on fisheries.

**Accidents:** An accidental oil spill has the potential to cause some detrimental effects on fisheries; however, it is unlikely that such an event would occur from the proposed activities (refer to **Item 5**, Water Quality). The effects of oil on mobile adult finfish or shellfish would likely be sublethal and the extent of damage would be reduced to the capacity of adult fish and shellfish to avoid the spill, to metabolize hydrocarbons, and to excrete both metabolites and parent compounds. The activities proposed in this plan will be covered by Cantium's Regional OSRP (refer to information submitted in **Section 9**).

There are no IPFs from emissions, or wastes sent to shore for disposal from the proposed activities which could cause impacts to fisheries.



## 7. Marine Mammals

GulfCet II studies revealed that cetaceans of the continental shelf and shelf-edge were almost exclusively bottlenose dolphin and Atlantic spotted dolphin. Squid eaters, including dwarf and pygmy killer whale, Risso's dolphin, rough-toothed dolphin, and Cuvier's beaked whale, occurred most frequently along the upper slope in areas outside of anticyclones. IPFs that could cause impacts to marine mammals as a result of the proposed operations in Breton Sound Block 55 include emissions, effluents, discarded trash and debris, and accidents.

**Emissions:** Noises from drilling activities, support vessels and helicopters may elicit a startle reaction from marine mammals. This reaction may lead to disruption of marine mammals' normal activities. Stress may make them more vulnerable to parasites, disease, environmental contaminants, and/or predation (Majors and Myrick, 1990). There is little conclusive evidence for long-term displacements and population trends for marine mammals relative to noise.

**Effluents:** Drilling fluids and cuttings discharges contain components which may be detrimental to marine mammals. Most operational discharges are diluted and dispersed upon release. Any potential impact from drilling fluids would be indirect, either as a result of impacts on prey items or possibly through ingestion in the food chain (API, 1989).

**Discarded trash and debris:** Both entanglement in, and ingestion of debris have caused the death or serious injury of marine mammals (Laist, 1997; MMC, 1999). The limited amount of marine debris, if any, resulting from the proposed activities is not expected to substantially harm marine mammals. Operators are prohibited from deliberately discharging debris as mandated by MARPOL-Annex V and the Marine Plastic Pollution Research and Control Act, and regulations imposed by various agencies including the United States Coast Guard (USCG) and the Environmental Protection Agency (EPA).

Cantium will operate in accordance with the regulations and also avoid accidental loss of solid waste items by maintaining waste management plans, manifesting trash sent to shore, and using special precautions such as covering outside trash bins to prevent accidental loss of solid waste. Special caution will be exercised when handling and disposing of small items and packaging materials, particularly those made of non-biodegradable, environmentally persistent materials such as plastic or glass.

Informational placards will be posted on all vessels and facilities having sleeping or food preparation capabilities. All offshore personnel, including contractors and other support services-related personnel (e.g. helicopter pilots, vessel captains and boat crews) will be indoctrinated on waste procedures, and will view the video (or Microsoft PowerPoint presentation), "Think About It" (previously "All Washed Up: The Beach Litter Problem"). Thereafter, all personnel will view the marine trash and debris training video annually. Offshore personnel will also receive an explanation from Cantium management or the designated lease operator management that emphasizes their commitment to waste management in accordance with NTL No. 2015-G03-BSEE.

**Accidents:** Collisions between support vessels and cetaceans would be unusual events, however should one occur, death or injury to marine mammals is possible. Contract vessel operators can avoid marine mammals and reduce potential deaths by maintaining a vigilant watch for marine mammals and maintaining a safe distance when they are sighted. Vessel personnel should use a Gulf of Mexico reference guide to help identify the twenty-one species of whales and dolphins, and the single species of manatee that may be encountered in the Gulf of Mexico OCS. Vessel personnel must report sightings of any injured or dead protected marine mammal species immediately, regardless of whether the injury or death is caused by their vessel, to the NMFS Southeast Marine Mammal Stranding Hotline at 1-877-433-8299 (<http://www.nmfs.noaa.gov/pr/health/report.htm#southeast>). Any injured or dead protected species should also be reported to [takereport.nmfs@noaa.gov](mailto:takereport.nmfs@noaa.gov). In addition, if the injury or death was caused by a collision with a contract vessel, the BOEM must be notified within 24 hours of the strike by email to [protectedspecies@bsee.gov](mailto:protectedspecies@bsee.gov). If the vessel is the responsible party, it is required to remain available to assist the respective salvage and stranding network as needed.

Oil spills have the potential to cause sublethal oil-related injuries and spill-related deaths to marine mammals. However, it is unlikely that an accidental oil spill would occur from the proposed activities (refer to **Item 5**, Water Quality). Oil spill response activities may increase vessel traffic in the area, which could add to changes in cetacean behavior and/or distribution, thereby causing additional stress to the animals. The effect of oil dispersants on cetaceans is not known. The acute toxicity of oil dispersant chemicals included in Cantium's OSRP is considered to be low when compared with the constituents and fractions of crude oils and diesel products. The activities proposed in this plan will be covered by Cantium's OSRP (refer to information submitted in accordance with **Section 9**).

There are no other IPFs (including physical disturbances to the seafloor) from the proposed activities which could impact marine mammals.

## **8. Sea Turtles**

IPFs that could cause impacts to sea turtles as a result of the proposed operations include emissions, effluents, discarded trash and debris, and accidents. GulfCet II studies sighted most loggerhead, Kemp's ridley and leatherback sea turtles over shelf waters. Historically these species have been sighted up to the shelf's edge. They appear to be more abundant east of the Mississippi River than they are west of the river (Fritts et al., 1983b; Lohofener et al., 1990). Deep waters may be used by all species as a transitory habitat.

**Emissions:** Noise from drilling activities, support vessels, and helicopters may elicit a startle reaction from sea turtles, but this is a temporary disturbance.

**Effluents:** Drilling fluids and cuttings discharges are not known to be lethal to sea turtles. Most operational discharges are diluted and dispersed upon release. Any potential impact from drilling fluids would be indirect, either as a result of impacts on prey items or possibly through ingestion in the food chain (API, 1989).

**Discarded trash and debris:** Both entanglement in, and ingestion of, debris have caused the death or serious injury of sea turtles (Balazs, 1985). The limited amount of marine debris, if any, resulting from the proposed activities is not expected to substantially harm sea turtles. Operators are prohibited from deliberately discharging debris as mandated by MARPOL-Annex V and the Marine Plastic Pollution Research and Control Act, and regulations imposed by various agencies including the United States Coast Guard (USCG) and the Environmental Protection Agency (EPA). Cantium will operate in accordance with the regulations and also avoid accidental loss of solid waste items by maintaining waste management plans, manifesting trash sent to shore, and using special precautions such as covering outside trash bins to prevent accidental loss of solid waste. Special caution will be exercised when handling and disposing of small items and packaging materials, particularly those made of non-biodegradable, environmentally persistent materials such as plastic or glass.

Informational placards will be posted on all vessels and facilities having sleeping or food preparation capabilities. All offshore personnel, including contractors and other support services-related personnel (e.g. helicopter pilots, vessel captains and boat crews) will be indoctrinated on waste procedures, and will view the video (or Microsoft PowerPoint presentation), “Think About It” (*previously “All Washed Up: The Beach Litter Problem”*). Thereafter, all personnel will view the marine trash and debris training video annually. Offshore personnel will also receive an explanation from Cantium management or the designated lease operator management that emphasizes their commitment to waste management in accordance with NTL No. 2015-G03-BSEE.

**Accidents:** Collisions between support vessels and sea turtles would be unusual events, however should one occur, death or injury to sea turtles is possible. Contract vessel operators can avoid sea turtles and reduce potential deaths by maintaining a vigilant watch for sea turtles and maintaining a safe distance when they are sighted. Vessel crews should use a reference guide to help identify the five species of sea turtles that may be encountered in the Gulf of Mexico OCS. Vessel crews must report sightings of any injured or dead protected sea turtle species immediately, regardless of whether the injury or death is caused by their vessel, to the State Coordinators for the Sea Turtle Stranding and Salvage Network (STSSN) at [http://www.sefsc.noaa.gov/species/turtles/stranding\\_coordinators.htm](http://www.sefsc.noaa.gov/species/turtles/stranding_coordinators.htm) (phone numbers vary by state). Any injured or dead protected species should also be reported to [takereport.nmfs@noaa.gov](mailto:takereport.nmfs@noaa.gov). In addition, if the injury or death was caused by a collision with a contract vessel, the BOEM must be notified within 24 hours of the strike by email to [protectedspecies@bsee.gov](mailto:protectedspecies@bsee.gov). If the vessel is the responsible party, it is required to remain available to assist the respective salvage and stranding network as needed.

All sea turtle species and their life stages are vulnerable to the harmful effects of oil through direct contact or by fouling of their food. Exposure to oil can be fatal, particularly to juveniles and hatchlings. However, it is unlikely that an accidental oil spill would occur from the proposed activities (refer to **Item 5**, Water Quality). Oil spill response activities may increase vessel traffic in the area, which could add to the possibility of collisions with sea turtles. The activities proposed in this plan will be covered by Cantium's Regional Oil Spill Response Plan (refer to information submitted in accordance with **Section 9**).

There are no other IPFs (including physical disturbances to the seafloor) from the proposed activities which could impact sea turtles.

## **9. Air Quality**

Breton Sound Block 55 is located approximately 8 miles from the Breton Wilderness Area and 8.7 miles from shore. Applicable emissions data is included in **Section 8** of the Plan.

There would be a limited degree of air quality degradation in the immediate vicinity of the proposed activities. Plan Emissions for the proposed activities do not exceed the annual exemption levels as set forth by BOEM. Accidents and blowouts can release hydrocarbons or chemicals, which could cause the emission of air pollutants. However, these releases would not impact onshore air quality because of the prevailing atmospheric conditions, emission height, emission rates, and the distance of Breton Sound Block 55 from the coastline. There are no other IPFs (including effluents, physical disturbances to the seafloor, wastes sent to shore for treatment or disposal) from the proposed activities which would impact air quality.

## **10. Shipwreck Sites (known or potential)**

IPFs that could cause impacts to known or unknown shipwreck sites as a result of the proposed operations in Breton Sound Block 55 are disturbances to the seafloor.

**Physical Disturbances to the seafloor:** Breton Sound Block 55 is located within the area designated by BOEM as high-probability for occurrence of shipwrecks. Cantium will report to BOEM the discovery of any evidence of a shipwreck and make every reasonable effort to preserve and protect that cultural resource.

**Accidents:** An accidental oil spill has the potential to cause some detrimental effects to shipwreck sites if the release were to occur subsea. However, it is unlikely that an accidental oil spill would occur from the proposed activities (refer to **Item 5**, Water Quality). The activities proposed in this plan will be covered by Cantium's Regional Oil Spill Response Plan (refer to information submitted in accordance with **Section 9**).

There are no other IPFs (including emissions, effluents, or wastes sent to shore for treatment or disposal) from the proposed activities that could cause impacts to shipwreck sites.

## **11. Prehistoric Archaeological Sites**

IPFs that could cause impacts to prehistoric archaeological sites as a result of the proposed operations in Breton Sound Block 55 are physical disturbances to the seafloor and accidents (oil spills).

**Physical Disturbances to the seafloor:** Breton Sound Block 55 is located inside the Archaeological Prehistoric high probability lines. Cantium will report to BOEM the discovery of any object of prehistoric archaeological significance and make every reasonable effort to preserve and protect that cultural resource.

**Accidents:** An accidental oil spill has the potential to cause some detrimental effects to prehistoric archaeological sites if the release were to occur subsea. However, it is unlikely that an accidental oil spill would occur from the proposed activities (refer to **Item 5**, Water Quality). The activities proposed in this plan will be covered by Cantium's Regional Oil Spill Response Plan (refer to information submitted in accordance with **Section 9**).

There are no other IPFs (including emissions, effluents, wastes sent to shore for treatment or disposal) from the proposed activities that could cause impacts to prehistoric archaeological sites.

## **Vicinity of Offshore Location**

### **1. Essential Fish Habitat (EFH)**

IPFs that could cause impacts to EFH as a result of the proposed operations in Breton Sound Block 55 include physical disturbances to the seafloor, effluents and accidents. EFH includes all estuarine and marine waters and substrates in the Gulf of Mexico.

**Physical disturbances to the seafloor:** The Live Bottom Low Relief Stipulation, the Live Bottom (Pinnacle Trend) Stipulation, and the Eastern Gulf Pinnacle Trend Stipulation would prevent most of the potential impacts on live-bottom communities and EFH from bottom disturbing activities (e.g., anchoring, structure emplacement and removal).

**Effluents:** The Live Bottom Low Relief Stipulation, the Live Bottom (Pinnacle Trend) Stipulation, and the Eastern Gulf Pinnacle Trend Stipulation would prevent most of the potential impacts on live-bottom communities and EFH from operational waste discharges. Levels of contaminants in drilling muds and cuttings and produced-water discharges, discharge-rate restrictions, and monitoring and toxicity testing are regulated by the EPA NPDES permit, thereby eliminating many significant biological or ecological effects. Operational discharges are not expected to cause significant adverse impacts to EFH.

**Accidents:** An accidental oil spill has the potential to cause some detrimental effects on EFH. Oil spills that contact coastal bays and estuaries, as well as OCS waters when pelagic eggs and larvae are present, have the greatest potential to affect fisheries. However, it is unlikely that an oil spill would occur from the proposed activities (refer to **Item 5**, Water Quality). The activities proposed in this plan will be covered by Cantium’s Regional OSRP (refer to information submitted in **Section 9**).

There are no other IPFs (including emissions, or wastes sent to shore for treatment or disposal) from the proposed activities which could impact essential fish habitat.

## **2. Marine and Pelagic Birds**

IPFs that could impact marine birds as a result of the proposed activities include air emissions, accidental oil spills, and discarded trash and debris from vessels and the facilities.

**Emissions:** Emissions of pollutants into the atmosphere from these activities are far below concentrations which could harm coastal and marine birds.

**Accidents:** An oil spill would cause localized, low-level petroleum hydrocarbon contamination. However, it is unlikely that an oil spill would occur from the proposed activities (refer to **Item 5**, Water Quality). Marine and pelagic birds feeding at the spill location may experience chronic, nonfatal, physiological stress. It is expected that few, if any, coastal and marine birds would actually be affected to that extent. The activities proposed in this plan will be covered by Cantium’s Regional OSRP (refer to information submitted in **Section 9**).

**Discarded trash and debris:** Marine and pelagic birds could become entangled and snared in discarded trash and debris, or ingest small plastic debris, which can cause permanent injuries and death. Operators are prohibited from deliberately discharging debris as mandated by MARPOL-Annex V and the Marine Plastic Pollution Research and Control Act, and regulations imposed by various agencies including the United States Coast Guard (USCG) and the Environmental Protection Agency (EPA). Cantium will operate in accordance with the regulations and also avoid accidental loss of solid waste items by maintaining waste management plans, manifesting trash sent to shore, and using special precautions such as covering outside trash bins to prevent accidental loss of solid waste. Special caution will be exercised when handling and disposing of small items and packaging materials, particularly those made of non-biodegradable, environmentally persistent materials such as plastic or glass. Informational placards will be posted on all vessels and facilities having sleeping or food preparation capabilities. All offshore personnel, including contractors and other support services-related personnel (e.g. helicopter pilots, vessel captains and boat crews) will be indoctrinated on waste procedures, and will view the video (or Microsoft PowerPoint presentation), “Think About It” (*previously “All Washed Up: The Beach Litter Problem”*). Thereafter, all personnel will view the marine trash and debris training video annually. Offshore personnel will also receive an explanation from Cantium management or the designated lease operator management that emphasizes their commitment to waste management in accordance with NTL No. 2015-G03-BSEE. Debris, if any, from these

proposed activities will seldom interact with marine and pelagic birds; therefore, the effects will be negligible.

There are no other IPFs (including effluents, physical disturbances to the seafloor, or wastes sent to shore for treatment or disposal) from the proposed activities which could impact marine and pelagic birds.

### **3. Public Health and Safety Due to Accidents.**

There are no IPFs (emissions, effluents, physical disturbances to the seafloor, wastes sent to shore for treatment or disposal or accidents, including an accidental H<sub>2</sub>S releases) from the proposed activities which could cause impacts to public health and safety. In accordance with NTL No.'s 2008-G04, 2009-G27, and 2009-G31, sufficient information is included in **Section 4** to justify our request that our proposed activities be classified by BSEE as H<sub>2</sub>S absent.

## **Coastal and Onshore**

### **1. Beaches**

IPFs from the proposed activities that could cause impacts to beaches include accidents (oil spills) and discarded trash and debris.

**Accidents:** Oil spills contacting beaches would have impacts on the use of recreational beaches and associated resources. Due to the response capabilities that would be implemented, no significant adverse impacts are expected. The activities proposed in this plan will be covered by Cantium's Regional OSRP (refer to information submitted in **Section 9**).

**Discarded trash and debris:** Trash on the beach is recognized as a major threat to the enjoyment and use of beaches. There will only be a limited amount of marine debris, if any, resulting from the proposed activities. Operators are prohibited from deliberately discharging debris as mandated by MARPOL-Annex V and the Marine Plastic Pollution Research and Control Act, and regulations imposed by various agencies including the United States Coast Guard (USCG) and the Environmental Protection Agency (EPA). Cantium will operate in accordance with the regulations and also avoid accidental loss of solid waste items by maintaining waste management plans, manifesting trash sent to shore, and using special precautions such as covering outside trash bins to prevent accidental loss of solid waste. Special caution will be exercised when handling and disposing of small items and packaging materials, particularly those made of non-biodegradable, environmentally persistent materials such as plastic or glass.

Informational placards will be posted on all vessels and facilities having sleeping or food preparation capabilities. All offshore personnel, including contractors and other support services-related personnel (e.g. helicopter pilots, vessel captains and boat crews) will be

indoctrinated on waste procedures, and will view the video (or Microsoft PowerPoint presentation), “Think About It” (*previously “All Washed Up: The Beach Litter Problem”*). Thereafter, all personnel will view the marine trash and debris training video annually. Offshore personnel will also receive an explanation from Cantium management or the designated lease operator management that emphasizes their commitment to waste management in accordance with NTL No. 2015-G03-BSEE.

There are no other IPFs (emissions, effluents, physical disturbances to the seafloor, or wastes sent to shore for treatment or disposal) from the proposed activities which could impact beaches.

## **2. Wetlands**

Salt marshes and seagrass beds fringe the coastal areas of the Gulf of Mexico. Due to the distance from shore (8.7 miles), accidents (oil spills) and discarded trash and debris represent IPFs which could impact these resources.

**Accidents:** Level of impact from an oil spill will depend on oil concentrations contacting vegetation, kind of oil spilled, types of vegetation affected, season of the year, pre-existing stress level of the vegetation, soil types, and numerous other factors. Light-oiling impacts will cause plant die-back with recovery within two growing seasons without artificial replanting. However, it is unlikely that an oil spill would occur from the proposed activities (refer to **Item 5**, Water quality). If a spill were to occur, response capabilities as outlined in Cantium’s Regional OSRP (refer to information submitted in **Section 9**) would be implemented.

**Discarded trash and debris:** There will only be a limited amount of marine debris, if any, resulting from the proposed activities. Operators are prohibited from deliberately discharging debris as mandated by MARPOL-Annex V and the Marine Plastic Pollution Research and Control Act, and regulations imposed by various agencies including the United States Coast Guard (USCG) and the Environmental Protection Agency (EPA). Cantium will operate in accordance with the regulations and also avoid accidental loss of solid waste items by maintaining waste management plans, manifesting trash sent to shore, and using special precautions such as covering outside trash bins to prevent accidental loss of solid waste. Special caution will be exercised when handling and disposing of small items and packaging materials, particularly those made of non-biodegradable, environmentally persistent materials such as plastic or glass.

Informational placards will be posted on all vessels and facilities having sleeping or food preparation capabilities. All offshore personnel, including contractors and other support services-related personnel (e.g. helicopter pilots, vessel captains and boat crews) will be indoctrinated on waste procedures, and will view the video (or Microsoft PowerPoint presentation), “Think About It” (*previously “All Washed Up: The Beach Litter Problem”*). Thereafter, all personnel will view the marine trash and debris training video annually. Offshore personnel will also receive an explanation from Cantium management or the designated lease operator management that emphasizes their commitment to waste management in accordance with NTL No. 2015-G03-BSEE.



There are no other IPFs (emissions, effluents, physical disturbances to the seafloor, or wastes sent to shore for treatment or disposal) from the proposed activities that could cause impacts to wetlands.

### **3. Shore Birds and Coastal Nesting Birds**

Breton Wilderness Area NWR/WA (8 miles from Breton Sound Block 55) is a highly productive habitat for wildlife. Thousands of shore birds use the refuge as a wintering area. Also, wading birds nest on the refuge. The NWR/WA provides habitat for colonies of nesting wading birds and seabirds as well as wintering shorebirds and waterfowl. The most abundant nesters are brown pelicans, laughing gulls, and royal, Caspian, and sandwich terns. IPFs from the proposed activities that could cause impacts to shore birds and coastal nesting birds are accidents (oil spills) and discarded trash and debris.

**Accidents:** Oil spills could cause impacts to shore birds and coastal nesting birds. The birds most vulnerable to direct effects of oiling include those species that spend most of their time swimming on and under the sea surface, and often aggregate in dense flocks (Piatt et al., 1990; Vauk et al., 1989). Coastal birds, including shorebirds, waders, marsh birds, and certain water fowl, may be the hardest hit indirectly through destruction of their feeding habitat and/or food source (Hansen, 1981; Vermeer and Vermeer, 1975). Direct oiling of coastal birds and certain seabirds is usually minor; many of these birds are merely stained as a result of their foraging behaviors. Birds can ingest oil when feeding on contaminated food items or drinking contaminated water.

Oil-spill cleanup operations will result in additional disturbance of coastal birds after a spill. However, it is unlikely that an oil spill would occur from the proposed activities (refer to **Item 5**, Water quality). Due to the distance from shore (8.7 miles), Cantium would immediately implement the response capabilities outlined in their Regional OSRP (refer to information submitted in **Section 9**).

**Discarded trash and debris:** Shore birds and coastal nesting birds are highly susceptible to entanglement in floating, submerged, and beached marine debris: specifically plastics. Operators are prohibited from deliberately discharging debris as mandated by MARPOL-Annex V and the Marine Plastic Pollution Research and Control Act, and regulations imposed by various agencies including the United States Coast Guard (USCG) and the Environmental Protection Agency (EPA). Cantium will operate in accordance with the regulations and also avoid accidental loss of solid waste items by maintaining waste management plans, manifesting trash sent to shore, and using special precautions such as covering outside trash bins to prevent accidental loss of solid waste. Special caution will be exercised when handling and disposing of small items and packaging materials, particularly those made of non-biodegradable, environmentally persistent materials such as plastic or glass.

Informational placards will be posted on vessels and every facility that has sleeping or food preparation capabilities. All offshore personnel, including contractors and other support services-related personnel (e.g. helicopter pilots, vessel captains and boat crews) will be

indoctrinated on waste procedures, and will view the video (or Microsoft PowerPoint presentation), “Think About It” (*previously “All Washed Up: The Beach Litter Problem”*). Thereafter, all personnel will view the marine trash and debris training video annually. Offshore personnel will also receive an explanation from Cantium management or the designated lease operator management that emphasizes their commitment to waste management in accordance with NTL No. 2015-G03-BSEE.

There are no other IPFs (emissions, effluents, physical disturbances to the seafloor, or wastes sent to shore for treatment or disposal) from the proposed activities that could cause impacts to shore birds and coastal nesting birds.

#### **4. Coastal Wildlife Refuges**

Breton Sound Block 55 is approximately 8 miles from the Breton Wilderness Area NWR/WA. Management goals of the NWR/WA are waterfowl habitat management, marsh restoration, providing sanctuary for nesting and wintering seabirds, and providing sandy beach habitat for a variety of wildlife species. IPFs from the proposed activities that could cause impacts to this coastal wildlife refuge are accidents (oil spills) and discarded trash and debris.

Impacts to shore birds and coastal nesting birds and to the beach, was covered in previous sections. Other wildlife species found on the refuges include nutria, rabbits, raccoons, alligators, and loggerhead turtles. Impacts to loggerhead turtles were also covered under a previous section.

**Accidents:** It is unlikely that an oil spill would occur from the proposed activities (refer to **Item 5**, Water quality). Response capabilities would be implemented, no impacts are expected. The activities proposed in this plan will be covered by Cantium’s Regional OSRP (refer to information submitted in **Section 9**).

**Discarded trash and debris:** Operators are prohibited from deliberately discharging debris as mandated by MARPOL-Annex V, the Marine Plastic Pollution Research and Control Act and regulations imposed by various agencies including the United States Coast Guard (USCG) and the Environmental Protection Agency (EPA). Cantium will operate in accordance with the regulations and also avoid accidental loss of solid waste items by maintaining waste management plans, manifesting trash sent to shore, and using special precautions such as covering outside trash bins to prevent accidental loss of solid waste. Special caution will be exercised when handling and disposing of small items and packaging materials, particularly those made of non-biodegradable, environmentally persistent materials such as plastic or glass.

Informational placards will be posted on vessels and every facility that has sleeping or food preparation capabilities. All offshore personnel, including contractors and other support services-related personnel (e.g. helicopter pilots, vessel captains and boat crews) will be indoctrinated on waste procedures, and will view the video (or Microsoft PowerPoint presentation), “Think About It” (*previously “All Washed Up: The Beach Litter Problem”*). Thereafter, all personnel will view the marine trash and debris training video annually. Offshore personnel will also receive an explanation from Cantium management or the designated lease operator management that emphasizes their commitment to waste management in accordance with NTL No. 2015-G03-BSEE.

There are no other IPFs (emissions, effluents, physical disturbances to the seafloor, or wastes sent to shore for treatment or disposal) from the proposed activities that could cause impacts to coastal wildlife refuges.

There are no other IPFs (emissions, effluents, physical disturbances to the seafloor, or wastes sent to shore for treatment or disposal) from the proposed activities that could cause impacts to coastal wildlife refuges.

## **5. Wilderness Areas**

**Accidents:** An accidental oil spill from the proposed activities could cause impacts to wilderness areas. However, it is unlikely that an oil spill would occur from the proposed activities (refer to **Item 5**, Water Quality). Due to the distance from the nearest designated Wilderness Area (8 miles) and the response capabilities that would be implemented, no significant adverse impacts are expected. The activities proposed in this plan will be covered by Cantium's Regional OSRP (refer to information submitted in **Section 9**).

**Discarded trash and debris:** Operators are prohibited from deliberately discharging debris as mandated by MARPOL-Annex V, the Marine Plastic Pollution Research and Control Act and regulations imposed by various agencies including the United States Coast Guard (USCG) and the Environmental Protection Agency (EPA). Cantium will operate in accordance with the regulations and also avoid accidental loss of solid waste items by maintaining waste management plans, manifesting trash sent to shore, and using special precautions such as covering outside trash bins to prevent accidental loss of solid waste. Special caution will be exercised when handling and disposing of small items and packaging materials, particularly those made of non-biodegradable, environmentally persistent materials such as plastic or glass.

Informational placards will be posted on vessels and every facility that has sleeping or food preparation capabilities. All offshore personnel, including contractors and other support services-related personnel (e.g. helicopter pilots, vessel captains and boat crews) will be indoctrinated on waste procedures, and will view the video (or Microsoft PowerPoint presentation), "Think About It" (previously "All Washed Up: The Beach Litter Problem"). Thereafter, all personnel will view the marine trash and debris training video annually. Offshore personnel will also receive an explanation from Cantium management or the designated lease operator management that emphasizes their commitment to waste management in accordance with NTL No. 2015-G03-BSEE.

There are no other IPFs (emissions, effluents, physical disturbances to the seafloor, or wastes sent to shore for treatment or disposal) from the proposed activities that could cause impacts to wilderness areas.

## **6. Other Environmental Resources Identified**

There are no other environmental resources identified for this impact assessment.

### **(C) IMPACTS ON PROPOSED ACTIVITIES**

The site-specific environmental conditions have been taken into account for the proposed activities. No impacts are expected on the proposed activities from site-specific environmental conditions.

### **(D) ENVIRONMENTAL HAZARDS**

During the hurricane season, June through November, the Gulf of Mexico is impacted by an average of ten tropical storms (39-73 mph winds), of which six become hurricanes (> 74 mph winds). Due to its location in the gulf, Breton Sound Block 55 may experience hurricane and tropical storm force winds, and related sea currents. These factors can adversely impact the integrity of the operations covered by this plan. A significant storm may present physical hazards to operators and vessels, damage exploration or production equipment, or result in the release of hazardous materials (including hydrocarbons). Additionally, the displacement of equipment may disrupt the local benthic habitat and pose a threat to local species.

The following preventative measures included in this plan may be implemented to mitigate these impacts:

1. Drilling & completion
  - a. Secure well
  - b. Secure rig / platform
  - c. Evacuate personnel

Drilling activities will be conducted in accordance with NTL No.'s 2008-G09, 2009-G10, and 2010-N10.

2. Platform / Structure Installation  
Operator will not conduct platform / structure installation operations during Tropical Storm or Hurricane threat.
3. Pipeline Installation  
Operator will not conduct pipeline installation operations during Tropical Storm or Hurricane threat.

### **(E) ALTERNATIVES**

No alternatives to the proposed activities were considered to reduce environmental impacts.

### **(F) MITIGATION MEASURES**

No mitigation measures other than those required by regulation will be employed to avoid, diminish, or eliminate potential impacts on environmental resources.

## **(G) CONSULTATION**

No agencies or persons were consulted regarding potential impacts associated with the proposed activities. Therefore, a list of such entities has not been provided.

## **(H) PREPARER(S)**

Matt Harlan  
J. Connor Consulting, Inc.  
19219 Katy Freeway, Suite 200  
Houston, Texas 77094  
281-578-3388  
matt.harlan@jcccteam.com

## **(I) REFERENCES**

Authors:

- American Petroleum Institute (API). 1989. Effects of offshore petroleum operations on cold water marine mammals: a literature review. Washington, DC: American Petroleum Institute. 385 pp.
- Balazs, G.H. 1985. Impact of ocean debris on marine turtles: entanglement and ingestion. In: Shomura, R.S. and H.O. Yoshida, eds. Proceedings, Workshop on the Fate and Impact of Marine Debris, 26-29 November 1984, Honolulu, HI. U.S. Dept. of Commerce. NOAA Tech. Memo. NOAA-TM-NMFS-SWFC-54. Pp 387-429.
- Burke, C.J. and J.A. Veil. 1995. Potential benefits from regulatory consideration of synthetic drilling muds. Environmental Assessment Division, Argonne National Laboratory, ANL/EAD/TM-43.
- Daly, J.M. 1997. Controlling the discharge of synthetic-based drilling fluid contaminated cuttings in waters of the United States. U.S. Environmental Protection Agency, Office of Water. Work Plan, June 24, 1997.
- Hansen, D.J. 1981. The relative sensitivity of seabird populations in Alaska to oil pollution. U.S. Dept. of the Interior, Bureau of Land Management, Alaska OCS Region, Anchorage. BLM-YK-ES-81-006-1792.
- Laist, D.W. 1997. Impacts of marine debris: entanglement of marine life in marine debris including a comprehensive list of species with entanglement and ingestion records. In: Coe, J.M. and D.B. Rogers, eds. Marine debris: sources, impacts, and solutions. New York, NY: Springer-Verlag. Pp. 99-139.

Majors, A.P. and A.C. Myrick, Jr. 1990. Effects of noise on animals: implications for dolphins exposed to seal bombs in the eastern tropical Pacific purse-seine fishery—an annotated bibliography. NOAA Administrative Report LJ-90-06.

Marine Mammal Commission. 1999. Annual report to Congress – 1998.

Piatt, J.F., C.J. Lensink, W. Butler, M. Kendziorek, and D.R. Nysewander. 1990. Immediate impact of the Exxon Valdez oil spill on marine birds. *The Auk*. 107 (2): 387-397.

Vauk, G., E. Hartwig, B. Reineking, and E. Vauk-Hentzelt. 1989. Losses of seabirds by oil pollution at the German North Sea coast. *Topics in Marine Biology*. Ros, J.D, ed. *Scient. Mar.* 53 (2-3): 749-754.

Vermeer, K. and R. Vermeer, 1975 Oil threat to birds on the Canadian west coast. *The Canadian Field-Naturalist*. 89:278-298.

Although not cited, the following were utilized in preparing this EIA:

- Hazard Surveys
- BOEM EIS's:
  - GOM Deepwater Operations and Activities. Environmental Assessment. MMS 2000-001
  - GOM Central and Western Planning Areas Sales 166 and 168 Final Environmental Impact Statement. MMS 96-0058.

## **SECTION 18 ADMINISTRATIVE INFORMATION**

### **18.1 EXEMPTED INFORMATION DESCRIPTION**

The proposed bottomhole locations of the planned wells have been removed from the Public Information copy of the DOCD as well as any discussions of the target objectives, geologic or geophysical data, and interpreted geology.